

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
RECEIVED 12-15-80
STATE CORPORATION COMMISSION

OCT 12 1982

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

CONSERVATION DIVISION
Wichita, Kansas

COUNTY ELLIS SEC. 19 TWP. 11S RGE. 18W E/W
Location as in quarters or footage from lines:
330' N of S line and 330' W of E line of the SE/4

Locate Well
correctly on above
Section Platt.

Lease Owner Robert R. Price Operating, Inc.
Lease Name Frisbie "M" Well No. 2
Office Address P.O. Box 45442, Tulsa, Oklahoma 74145
Character of Well (Completed as Oil, Gas or Dry Hole): Oil
Date Well Completed 6-30-43
Application for plugging filed 8-17-82
Plugging commenced 1:30 P.M. October 4, 1982
Plugging completed 3:30 P.M. October 4, 1982
Reason for abandonment of well or producing formation _____

Collapsed casing at 1800', Parted at 900'
Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Dennis Hamil - Plainville
Producing formation Topeka Depth to top 3101' bottom 3268' T.D. 3304'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
<u>Arbuckle</u>	<u>oil</u>	<u>3607</u>	<u>3619</u>	<u>10"</u>	<u>90'</u>	<u>None</u>
<u>Lansing-Kansas City</u>	<u>oil</u>	<u>3342</u>	<u>3400</u>	<u>5"</u>	<u>3607'</u>	<u>None</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from 3607 feet to Surface feet for each plug set.

500 sx. of 50-50 pozmix plus 2% gel was pumped into 5 1/2" casing at 200#. With 1800' of tubing in the casing, 79 barrels of cement slurry were required to fill the casing to surface. A total of 130 barrels of slurry were used indicating that 50 barrels of slurry was squeezed out of the casing and into the formations. Casing was standing full of cement after 24 hours.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sun Oilwell Cementing, Inc.

STATE OF OKLAHOMA COUNTY OF TULSA, ss.

ROBERT R. PRICE (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Robert R. Price
P.O. Box 45442, Tulsa, Ok 74145
(Address)

SUBSCRIBED AND SWORN TO before me this 8th day of October, 1982

Verona Dady
Notary Public.

My Commission expires: Feb. 5, 1985