

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Bldg.  
Wichita, Kansas 67202

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit

COUNTY Ellis SEC. 19 TWP. 11 RGE. 18 E/W  
Location as in quarters or footage from lines:  
NW SE NW


Lease Owner National Development Co.  
Lease Name FRISBIE Well No. #1  
Office Address 833 North Waco Wichita, KS 67203  
Character of Well (Completed as Oil, Gas or Dry Hole):  
Date Well Completed 5-28-82  
Application for plugging filed 5-28-82  
Plugging commenced 5-28-82  
Plugging completed 5-28-82  
Reason for abandonment of well or producing formation \_\_\_\_\_

Locate Well  
correctly on above  
Section Platt.

Was permission obtained from the Conservation Division or it's  
Agent's before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Gilbert Scheck  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom T.D. 3585'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out

Describe in detail the manner in which the well was plugged, indicating where the mud  
fluid was placed and the method or methods used in introducing it into the hold. If cement  
or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet  
to \_\_\_\_\_ feet for each plug set.

Bottom Plug: @ 750' w/70 sacks 50/50 pozmix 4% gel 3% cc. thru drill pipe  
Middle Plug: @ 270' w/40 " " " " " " "  
Top Plug: @ 40' w/solid bridge of 1/2 sack hulls & 8-5/8" plug & 10 sacks cement  
10 sacks cement in Rat Hole

RECEIVED  
STATE CORPORATION COMMISSION

6-7-82

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Duke Drilling Co., Inc.

STATE OF Kansas COUNTY OF Barton, ss.  
Bill Draney (employee of owner) or (owner or operator)

above-described well, being first duly sworn on oath, says: That I have knowledge of the  
facts, statements, and matters herein contained and the log of the above-described well as  
filed and that the same are true and correct. So help me God.

(Signature) Bill Draney  
Box 823 Great Bend, KS 67530  
(Address)

SUBSCRIBED AND SWORN TO before me this 31 day of May, 1982

Dorothy M. Hague  
Notary Public.

My Commission expires: 4-29-86

DRILLERS WELL LOG

DATE COMMENCED: May 22, 1982  
DATE COMPLETED: May 29, 1982

National Development Co.  
FRISBIE #1  
NW SE NW  
Sec. 19, T11S, R18W  
Ellis County, Ks.

ELEVATION: 1958 K.B.

0 - 1274'	Surface Soil, Post Rock, Shale
1274 - 1318'	Anhydrite
1318 - 2968'	Shale & Lime
2968 - 3196'	Lime
3196 - 3237'	Shale
3237 - 3499'	Lime
3499 - 3581'	Shale, Lime, Chert, Sand
3581 - 3585'	Dolomite
3585'	RTD

FORMATION DATA

Anhydrite	1274'
Topeka	2968'
Neobner	3196'
Lansing K.C.	3237'
Base K.C.	3435'
Conglomerate	3499'
Arbuckle	3581'
RTD	3585'

3237  
1958  
-1274

3581  
1958  
-1274

Surface Pipe: Set new 8-5/8"  
23" pipe at 258' w/160 sacks  
60/40 pozmix, 2% gel 5% ce.

A F F I D A V I T

STATE OF KANSAS  
COUNTY OF BARTON) ss

Bill Draney of lawful age, does swear and state that the facts and  
statements herein are true and correct to the best of his knowledge.

Bill Draney

Subscribed and sworn to before me this 3rd day of June 1982.

My Comm. Expires:

4-29-86

Harold M. Haque  
Notary Public

RECEIVED  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION  
Wichita, Kansas