

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-051-24,876-0000

LEASE NAME Frisbie

WELL NUMBER #1-19

3,630 Ft. from S Section Line

330 Ft. from E Section Line

SEC. 19 TWP. 11 RGE. 18 (X) or (W)

COUNTY Ellis

Date Well Completed 8-26-94

Plugging Commenced 8-26-94

Plugging Completed 8-26-94

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Halliburton Oil Producing Co.

ADDRESS 525 Central Park Drive, #1-210

Oklahoma City, OK. 73105

PHONE#(405) 525-3371 OPERATORS LICENSE NO. 5988

Character of Well D & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 8-26-94 (date)

by Bruce Basye (KCC District Agent's Name).

Is ACO-1 filled? No If not, is well log attached? Yes

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 3,690'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	299'	Cmtd. w/190 sax

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.
Push bridge plug to 3,600', fill hole w/heavy mud. Push bridge plug to 1,390', spot 25 sax cement on plug thru drill pipe. Push bridge plug to 580', spot 75 sax cement on plug thru drill pipe. Push bridge plug to 350', spot 40 sax cement on plug. Push plug to 40', dump 10 sax on plug. Push plug to 40', dump 10 sax cement on plug to cellar. Dump 10 sax down mouse hole and 15 sax down rat hole.
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Shields Drilling Co. License No. 5184

Address Box 709, Russell, Kansas 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Halliburton Oil Producing Co.

STATE OF KANSAS COUNTY OF RUSSELL, ss.

Jack P. Beeman Contractor
(Employee of ~~operator~~) or (~~operator~~) of
above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jack P. Beeman, Sr. - Pres

(Address) Box 709, Russell, Kansas 67665

SUBSCRIBED AND SWORN TO before me this 9th day of September

My Commission Expires:



Ruth Phillips
Notary Public

Notary Public

RECEIVED
SEP 13 1994
CORPORATION COMMISSION

Form CP-94
Revised 05-88




Shields

Russell, Kansas

WELL LOG

Operator: Halliburton Oil Producing Co.
 Well: Frisbie #1-19
 Commenced: August 17, 1994
 Completed: August 26, 1994
 Contractor: Shields Drilling Co.

Well Description: NE SE NE
 Sec. 19-11S-18W
 Ellis County, KS.



CASING RECORD

Size	Run	Pulled
8 5/8"	299'	Cmtd. w/190 sax

Elevation: 2,077' KB
 Treatment:
 Production: D & A
 Tops:

..... Figures Indicate Bottom of Formations

Post rock	26'	
Post rock & shale	302'	
Shale	480'	
Shale & sand	1,379'	
Anhydrite	1,417'	
Shale	2,090'	
Shale & lime	3,211'	
Lime	3,690'	RTD

RECEIVED
 STATE CORPORATION COMMISSION

SEP 13 1994

DIVISION
 KANSAS

Notes