


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Ellis County, Sec. 19 Twp. 11 Rge. 18 (~~EX~~) (W)
Location as "NE/CNW&SW&" or footage from lines E/2 E/2 SE/4
Lease Owner Francis Oil & Gas Inc.
Lease Name Richards Well No. 3-113
Office Address 905 Palace Bldg. Tulsa, Okla.
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed Dec. 13, 1957 19
Application for plugging filed Dec. 13, 1957 19
Application for plugging approved Dec. 13, 1957 19
Plugging commenced Dec. 13, 1957 19
Plugging completed Dec. 13, 1957 19
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3674 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	310' w/175 sacks	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with mud to 700'; set plug at 700' with 20 sacks cement;
mud to 200', set plug at 300' with 1/2 sack hulls, 20 sacks cement;
top plug set at 40' with 1/2 sack hulls, 10 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION

DEC 21 1957

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Veeder Supply and Development Co.
Address Box 201, Cherryvale, Kansas

STATE OF Kansas, COUNTY OF Montgomery, ss.
C. H. Woods (employee of owner) or (Contractor) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. H. Woods
Cherryvale, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 16th day of December, 1957

My commission expires July 11, 1960. Oliver Lawson Notary Public.

PLUGGING
FILE NO. 19.T.11 R184
BOOK PAGE 69 LINE 28

Veeder Supply & Dev'l. Co.



Cherryvale, Kansas

Drilled for Francis Oil & Gas Inc.
Herman Geo. Kaiser Farm Richards No 3-D Depth 367h
 Contractor Veeder Supply & Development Co. Pipe 310' 8 5/8" csg. w/175 sacks
 Location E/2 E/2 SE/4 Sec 19 Twp. 11 Range 18W
 Commenced 12-2-1957 Completed 12-14-1957 County Ellis State Kansas

Yellow rock	0	110	110	elevation: 2101 DF
Blue shale	110	310	200	
Shale	310	640	330	Tops:
Shale and sand	640	925	285	Kansas City 3363'
Sand and shale	925	1120	195	Base KC 3594
Shale	1120	1135	15	Arbuckle 3664
Shale, red bed	1135	1407	272	
Anhydrite	1407	1448	41	
Shale and shells	1448	2015	567	
Shale and lime streaks	2015	2075	60	
Shale and lime	2075	2405	330	
Lime and shale	2405	2755	350	
Shale and lime streaks	2755	2910	155	
Shale and lime	2910	3100	190	
Lime and shale	3100	3220	120	
Lime	3220	3594	374	
Conglomerate	3594	3635	41	
Lime, shale, chert	3635	3660	25	
Lime	3660	3664	4	
Arbuckle	3664	3674	10	
T. D.	3674			

Dry and abandoned

RECEIVED
 STATE CORPORATION COMMISSION
 DEC 21 1957
 CONSERVATION DIVISION
 Wichita, Kansas

AFFIDAVIT

STATE OF KANSAS)
 Montgomery County) SS

C. H. Woods, of lawful age, being first duly sworn on oath, deposes and says:

THAT he has read the above drilling log covering the Richards #3-D well located in Section 19-11-18W. Ellis County, Kansas, and that the same is true and correct. Further affiant saith not.

THE VEEDER SUPPLY AND DEVELOPMENT CO.

BY C. H. Woods
 C. H. Woods

Subscribed and sworn to before me this 16th day of December, 1957.

Loles Lawson
 Notary Public

My commission expires July 11, 1960.

PLUGGING
 FILED REG 19 T 11 R 18 W
 BOOK PAGE 69 LINE 28