


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Ellis County, Sec. 27 Twp. 11 Rge. 18 (W) (W)
Location as "NE/CNW&SW" or footage from lines NE cor.
Lease Owner Woodman-Bannitti and Brown & Fortier
Lease Name Henderson Well No. 1
Office Address P. C. Box 387, Moisington, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 12-1-1957
Application for plugging filed 12-1-1957
Application for plugging approved 12-1-1957
Plugging commenced 12-1-1957
Plugging completed 12-1-1957
Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes.

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3720 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	204	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy rotary mud. Bottom plug 450' with 20 sacks cement. Middle plug 180' with 20 sacks cement. Top plug 40' with 1/3 sack hulls preceding it and 10 sacks cement.

12-3-57

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sun Cementing Company
Address Hays, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
K. T. Woodman (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) K. T. Woodman

717 Union National Bldg., Wichita 2, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 2nd day of December, 1957

Mildred E. Lick
Mildred E. Lick, Notary Public.

My commission expires March 15, 1961

PLUGGING
FILE SEC. 27 T. 11 R. 18 W.
BOOK PAGE 65 OF 16

DRILLING LOG

Company: Woodman & Iannitti Drilling Co. and Brown & Fortier
 Lease: #1 Henderson NE corner Sec. 27-11-18W
 Ellis County, Kansas
 Contractor: Woodman & Iannitti Drilling Company
 P. O. Box 387, Hoisington, Kansas
 Date Commenced: November 22, 1957
 Date Completed: December 1, 1957
 Total Depth: 3720'
 Casing: 8 5/8" cemented at 204 with 125 sacks cement

Figures Indicate the Bottom of Formation

0 - 100	Post Rock	3105	Shale & Lime
204	Sand & Blue Shale	3655	Lime
670	Shale	3662	Chert
785	Sand	3685	Simpson
870	Shale	3690	Arb. Dolo.
1045	Sand	3720	Arb. Dolo. T.D.
1090	Shale & Sand		
1388	Redbed - Shale		
1427	Anhydrite		
1450	Redbed - Shale		
1700	Shale & Shells		
2000	Shale & Shells		
2270	Shale - Lime		
2465	Lime		
2590	Lime - Shale		
2725	Shale & Lime		
2845	Shale & Lime		
2950	Lime - Shale		

GEOLOGICAL TOPS

Elevation	2106 RB
Anhydrite	1385 721
Heebner	3319 -1213
Toronto	3338 -1232
Lansing	3363 -1257
Conglomerate	3632 -1526
Simpson Shale	3662 -1557
Arbuckle	3688 -1582
Total Depth	3720 -1614

I certify the above to be a true and correct copy of the Driller's Log and Geological Tops to the best of my knowledge and belief.

WOODMAN & IANNITTI DRILLING CO.

By: K. T. Woodman
 K. T. Woodman

PLUGGING			
FILE	SEC. 27	T. 11	R. 18W
BOOK	PAGE 65	LINE	16