

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

OR
FORMATION PLUGGING RECORD

Strike out upper line
when reporting plug-
ging off formations.

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
300 Bitting Building
Wichita, Kansas

ELLIS County. Sec. 27 Twp. 11 Rge. 18 (E) (W)

Location as "NE 1/4 NW 1/4 SW 1/4" or footage from lines. NE NE

Lease Owner. MAZDA OIL CORP.

Lease Name. HENDERSON Well No. C-1

Office Address. TULSA, OKLA.

Character of Well (completed as Oil, Gas or Dry Hole). DRY HOLE

Date well completed. 8/23 19. 46

Application for plugging filed. 8/22 19. 46

Application for plugging approved. 8/22 19. 46

Plugging commenced. 8/22 19. 46

Plugging completed. 8/22 19. 46

Reason for abandonment of well or producing formation. DRY HOLE

If a producing well is abandoned, date of last production. 19.

Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well. KERN

Producing formation. Depth to top. Bottom. Total Depth of Well. 3771 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8"	1399'	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from... feet to ... feet for each plug set.

FILLED HOLE WITH MUD TO 500' - PLUG & 20 SACKS CEMENT -
FILLED HOLE WITH MUD TO 20' - PLUG & 10 SACKS CEMENT.

8-30-46

PLUGGING
FILE 27 11-18W
BOOK 68 PAGE 12

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to. MAZDA OIL CORP.
Address. TULSA, OKLA.

STATE OF KANSAS, COUNTY OF RUSSELL, ss.

C. L. ROBERTS (employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]

RUSSELL (Address)

SUBSCRIBED AND SWORN TO before me this 29th day of August, 1946

My commission expires July 2, 1949
Genevieve Poole Notary Public.

MAZDA OIL CORPORATION
HENDERSON O-1

SEC. 27 Twp. 11 Rge. 18
OSHPYI ELLIS, KANSAS

TOTAL DEPTH: 3771'
Comm: 7/31/46 Comp: 8/23/46

TOP LANSING-K.C. - 3368
TOP CONGLOMERATE - 3627
TOP ARBUCKLE - 3765

CASING
67 Jts. 8 5/8" SET AT 1399


CEMENT
550 BX

FORMATION DEPTH

LIME & GRAVEL	100'
SHALE	165
SHALE	190
SAND	220
SHALE & SHELLS	565
SAND & ST. OF IRON	785
SHALE & SHELLS	790
BLUE SHALE	840
SAND & SHALE	1050
SHALE	1115
SAND	1115
RED ROCK & SHELLS	1170
RED BED & SHELLS	1260
RED ROCK	1320
RED BED, SHALE & IRON	1385
RED ROCK	1390
AMMONITE	1425
SHALE & RED BED	1440
RED BED, BLUE SHALE & SHELLS	1730
SALT & SHELLS	1755
SALT & SHALE	1925
SHALE & SHELLS	2040
SANDY LIME	2060
LIME	2115
SHALE & LIME	2235
LIME	2330
LIME & SHALE	2530
RED BED & SHALE	2560
LIME	2715
LIME & SHALE	2800
BRICK LIME	2808
NAPO LIME	2840
LIME & SHALE	3055
LIME	3215
LIME & SHALE	3255
LIME	3628
CONGLOMERATE	3670
CONGLOMERATE & CHERT	3720
CHERT CONG.	3736
CONG. & CHERT	3765
ARBUCKLE	3771

27 11.2180
68 122

STATE OF KANSAS)
) SS
RUSSELL COUNTY)



I HEREBY CERTIFY THAT THE ABOVE INFORMATION IS TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE.

Larry C. Froelich

SUBSCRIBED AND SWORN TO BEFORE ME THIS 28TH DAY OF AUGUST, 1946.

Clara Hummel
NOTARY PUBLIC

My Commission Expires 6/17/50