


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Ellis County, Sec. 27 Twp. 11 Rge. 18W (Box (W))
Location as "NE/CNW/SW" or footage from lines SW NE NW

NORTH



Locate well correctly on above
Section Plat

Lease Owner Don Brown
Lease Name Henderson Well No. G-5
Office Address 2311 Liberty Bk. Bldg. Oklahoma City, Oklahoma
Character of Well (completed as Oil, Gas or Dry Hole) Oil-depleted
Date well completed August 12, 1949
Application for plugging filed March 9, 1959
Application for plugging approved March 10, 1959
Plugging commenced March 27, 1959
Plugging completed March 27, 1959
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3630' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

8 5/8" at 1382' -circ-with 650 sacks cement - 5 1/2" 3620' with 100 sacks cement behind.
Filled hole with sand to 3610' set 4 sacks cement with dump bailer, pulled 2970' 5 1/2" to 600', circulated hole with heavy mud (Gel) through 5 1/2" at 600', displaced 25 sacks cement through 5 1/2" at 600', heavy mud to 210', displaced 20 sacks cement through 5 1/2" at 210', heavy mud to 35' set rock and 10 sacks cement to bottom cellar.

Mudding and cementing by West Supply Company pump truck.

RECEIVED
STATE CORPORATION COMMISSION
FEB 9 1965
CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor West Supply Company
Address Chase, Kansas

STATE OF KANSAS, COUNTY OF RICE, ss.
Noel J. Knight (employee of owner) or (~~SECRETARY~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight
Chase, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 1st day of February, 1965

My commission expires May 20, 1968

Milton J. Vilis
Notary Public.

Langston Expl. Co

Contractor: Harbar Drilling Company

HENDERSON G-5

SW 1/4 NE 1/4 NW 1/4 Sec. 27-11S-18W, Ellis County, Kansas

Rigging up Rotary Tools 7-21-49
 Tearing out Rotary Tools 8-6-49
 Rigging up Cable Tools 8-6-49
 Tearing out Cable Tools 8-12-49

Run 68 Jts 8 5/8" surface pipe.
 Set @ 382' and cemented with 650
 sacks of cement.
 Run 118 Jts 5 1/2" casing. Set @ 364'
 and cemented with 100 sacks of cement.

FORMATION

FROM

TO

Rock and gravel
 Shale
 Shale and shell
 Dakota Sand
 Sand and shale
 Shale
 Anhydrite
 Red Bed
 Shale
 Shale and broken lime
 Shale and lime
 Lime and shale
 Lime
 Lime and shale
 Lime
 Lime and shale - Arbuckle

0
 70
 310
 550
 995
 1350
 1370
 1420
 1510
 1980
 1980
 2125
 2255
 2255
 3070
 3274
 3300
 3495

70
 310
 550
 995
 1350
 1370
 1420
 1510
 1980
 2125
 2255
 3070
 3274
 3300
 3495

Total depth

Tubing: 2" 3602'
 Potential 1,924 B/D Net.
 No Water
 Acid: ~~None~~ 500 gal

I, Don S. Packer, hereby certify that the above log is true and correct, to the best of my knowledge and belief.

Don S. Packer

Subscribed and sworn to before me this 22nd day of August, 1949.

Walter Kelly
 Notary Public

My commission expires: March 22, 1952.

RECEIVED
 STATE CORP

MAR 9 1959
 CONSERVATION DIVISION
 Wichita, Kansas

PLUGGING
 FILE SEC. 27 T 11 R 18W
 BOOK PAGE 19 LINE 35