

STATE OF KANSAS
STATE CORPORATION COMMISSION


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

OR
FORMATION PLUGGING RECORD

Strike out upper line
when reporting plug-
ging of formations.

NORTH



Locate well correctly on above
Section Plat

ELLIS County. Sec. 27 Twp. 11 Rge. 18 (E) (W)
Location as "NE1/4NW1/4SW1/4" or footage from lines. SWC
Lease Owner. MAZDA OIL CORP.
Lease Name. HENDERSON Well No. D-1
Office Address. TULSA, OKLA.
Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE
Date well completed. 12/13/46 19
Application for plugging filed. 12/13/46 19
Application for plugging approved. 12/13/46 19
Plugging commenced. 12/13/46 19
Plugging completed. 12/13/46 19
Reason for abandonment of well or producing formation. DRY HOLE
If a producing well is abandoned, date of last production. 19
Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? YES

Name of Conservation Agent who supervised plugging of this well.
Producing formation. Depth to top. Bottom. Total Depth of Well. 3735' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS


CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8"	1400'	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

PLUG TO 250' AND 15 SACKS CEMENT - FILL HOLE W/ MUD TO 20' - SET
PLUG AND 10 SACKS CEMENT.

27 11 18W
87 31



(If additional description is necessary, use BACK of this sheet)
Correspondence regarding this well should be addressed to MAZDA OIL CORPORATION
Address. TULSA 1, OKLA.

STATE OF KANSAS, COUNTY OF RUSSELL, SS.
C. L. ROBERTS (employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-
described well as filed and that the same are true and correct. So help me God.

(Signature) *C. L. Roberts*

RUSSELL, KS.
(Address)

SUBSCRIBED AND SWORN TO before me this 13TH day of DECEMBER, 1946.

Clara Lumme
Notary Public.

My commission expires 6/17/50

MAZDA OIL CORPORATION
NEEDHAM D-1

SEC. 27 Twp. 11 Rng. 18
COUNTY: ELLIS, KANSAS

TOTAL DEPTH 3735'
Comm 11/23/46
Comp 12/13/46

TOP LANSING KB - 3366'
TOP CHERTY COND - 3660
TOP ANNEVILLE - 3702

CASING
66 Jts. 8 5/8" SET AT 1400'

535 BAGS CEMENT

FORMATION	DEPTH
ROCK & SHALE	40'
SHALE & SHELLS	515
SAND	560
SAND & SAND	620
SAND	725
SHALE & SHELLS	1075
SAND	1095
RED BED, SHELLS, IRON	1315
RED BED & SHALE	1392
ANHYDRITE	1440
SHALE & RED BED	1635
SHALE, SHELLS, STD. OILY	1775
SALT & SHELLS	1830
SHALE & SHELLS	2000
LIME & SHALE	2365
LIME	2450
LIME & SHALE	2575
LIME & SAND	2645
LIME, SANDY LIME	2710
LIME & SHALE	2855
LIME	2865
SHALE	2895
LIME	2921
LIME & SHALE	3110
LIME	3258
SHALE & SHELLS	3274
LIME	3310
LIME & SHALE	3366
LIME	3630
LIME & SHALE	3660
CHERTY CONGLOMERATE	3702
LIME	3735

STATE OF KANSAS)
) SS
RUSSELL COUNTY)

27 11 18W
87 31

I HEREBY CERTIFY THAT THE ABOVE INFORMATION IS TRUE AND
CORRECT TO THE BEST OF MY KNOWLEDGE.

Larry C. Fruehlich

SUBSCRIBED AND SWORN TO BEFORE ME THIS 16TH DAY OF DECEMBER, 1946.

Clara L. Turner
NOTARY PUBLIC

MY COMM. EXPIRES 6/17/50