

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-62-3-117

API NUMBER 15-051-20,335-A ⁶⁰⁻⁰¹

LEASE NAME Johnson "D"

RECEIVED

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 2

2,970 Ft. from S Section Line

3,300 Ft. from E Section Line

AUG 10 2001

LEASE OPERATOR Koenig Inc.

SEC. 32 TWP. 11 RGE. 18 (E) or (W)

ADDRESS P. O. Box 234 Hays, KS 67601-0234

COUNTY Ellis

PHONE (785) 625-6711 OPERATORS LICENSE NO. 09346

Date Well Completed November 1968

Character of Well oil

Plugging Commenced 7/24/01

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 7/25/01

The plugging proposal was approved on 7/23/01 (date)

by Herb Deines (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? _____

Producing Formation Topeka, LKC, Arb Depth to Top 3,124 Bottom 3,631 T.O. 3,633

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
		0	216	8-5/8"	216	-0-
		0	3633	4"	3,633	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set. Hook up to 8-6/8" and pump 25 sacks cement. Pressure to 450# and held. Hook up to 4 1/2" casing and pump 225 sacks 60/40 10% gel with 600# hulls. Maximum pressure 350#. Shut in with 150#. Top off 4 1/2" casing with 2 yards redimix.

Name of Plugging Contractor Swift Services, Inc. License No. 32382

Address P. O. Box 466 Ness City, KS 67560

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Glenn D. Diehl, President, Diehl Oil, Inc.

STATE OF Kansas COUNTY OF Ellis, ss.

Glenn D. Diehl (Employee of Operator) or (Operator) c above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.


(Signature) [Signature]

(Address) P. O. Box 234 Hays, KS 67601

SUBSCRIBED AND SWORN TO before me this 9th day of August, 2001

[Signature]
Notary Public

My Commission Expires: 10-16-03



Form CP-
Revised 05-8:

OR