

API NUMBER 15-051-21,896-0000

LEASE NAME Johnson "N"

WELL NUMBER 1

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

5050 Ft. from S Section Line

4950 Ft. from E Section Line

SEC. 32 TWP. 11S. RGE. 18 or (W)

COUNTY Ellis

Date Well Completed 7-3-80

Plugging Commenced 11-19-85

Plugging Completed 11-19-85

LEASE OPERATOR Champlin Pet. Co.

ADDRESS 6441 NW Grand Blvd., Ste. 300

PHONE# 405 840 3521 OPERATORS LICENSE NO. 6417

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City (Carl Goodrow)

Is ACO-1 filed? Yes If not, is well log attached? \_\_\_\_\_

Producing Formation Topoka, Lansing-Kf. Depth to Top 3072 Bottom 3454 T.D. 3800

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Lansing-Kf "H"		3448	3454	8 5/8"	239'	0
Topoka		3072	3262	5 1/2"	3799'	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Pump 25 Sk. 60-90 Poz-Mix Cement w/ 6 3/8" 32 G.C. w/ 5 Sk. bulls mixed in Cement followed w/ 15 Sk. Gal + 125 Sk. Cement Pressured to 800'. Shut well in. Pump in Annulus. Hit Press. immediately. Cut off Esp. & Cap well.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Howco License No. N/A

Address P.O. Box 1598, Liberal, ks. 67901

STATE OF Okla. COUNTY OF Okla., ss.

J. L. Ford (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) J. L. Ford

(Address) 6441 NW Grand Blvd., Ste. 300

Okla. City, Ok day of Jan, 19 86

Myra A. Quinn Notary Public

My Commission Expires: 10-08-87



DRILLERS LOG

No. 1 Johnson 'N'

CASING RECORD:	COMPANY:	Champlin Petroleum Company	DESCRIPTION:
8 5/8" @ 238.60' w/200 sx cement	CONTRACTOR:	Red Tiger Drilling Company	100' N of NW/4 NW/4 NW/4 Sec. 32-T11S-R18W Ellis County, Kansas
5 1/2" @ 3,799' w/200 sx cement	COMMENCED:	May 13, 1980	
	COMPLETED:	May 23, 1980	
TOTAL DEPTH: 3,800'			ELEVATION:

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Rock	0	44	
Shale	44	860	
Sand	860	1065	
Shale	1065	1115	
Red Bed	1115	1385	
Anhydrite	1385	1420	
Shale	1420	2035	
Shale & Lime	2035	2238	
Lime & Shale	2238	2769	
Lime	2769	3800	
RTD		3800	

I certify that this is a true and correct copy of the above log to the best of my knowledge.

RED TIGER DRILLING COMPANY

Gloria Fawcett  
Gloria Fawcett


Subscribed and sworn to before me this 28th day of May, 1980.

Joyce A. Hagermann  
Notary Public

RECEIVED  
STATE CORPORATION COMMISSION

APR 09 1984

CONSERVATION DIVISION  
Wichita, Kansas

 Joyce A. Hagermann  
NOTARY PUBLIC  
Sedgwick County, Kansas  
My Appl Exp 12-18-80