


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

WELL PLUGGING RECORD

Ellis County. Sec 32 Twp 11 S Rge 18 (E) W (W)

Location as "NE/CNWxSWx" or footage from lines SE SE NE
Lease Owner Shelley-Miller Drilling Company
Lease Name Johnson Well No. 1
Office Address 205 Miller Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed November 19 19 61
Application for plugging filed November 19 19 61
Application for plugging approved November 19 19 61
Plugging commenced November 19 19 61
Plugging completed November 19 19 61
Reason for abandonment of well or producing formation Failure to produce
in commercial quantities
If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? Yes



Locate well correctly on above
Section Plat

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3672 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	225'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Bottom Plug 540' 20 sacks cement
Second Plug 210' 20 sacks cement
Top Plug 40' Filled hole with 1/2 sack hulls and cement

11-22-61

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor _____
Address _____

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Richard A. Shelley (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Richard A. Shelley
205 Miller Building, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 21st day of November, 19 61

James M. Powers
Notary Public.

My commission expires March 24, 1964



COMPANY: Shelley-Miller Drilling Company
 205 Miller Building
 Wichita, Kansas

Rotary Drilling Commenced: 11- 7-61
 Rotary Drilling Completed: 11-19-61

LOCATION: Johnson No. 1
 SE SE NE Sec. 32-11S-18W
 Ellis County, Kansas

CONTRACTOR: Shelley-Miller Drilling Company
 205 Miller Building
 Wichita, Kansas

CASING RECORD: 8 5/8" used 28 lb casing set @ 225' cemented with 150 sacks

LOG

(Measurements from top of Rotary Bushing to bottom of formation)

Surface hole	125
Shale	225
Shale & Shell	550
Red Bed and soft lime	675
Shale & Lime	1,150
Shale & Red Bed	1,370
Red Bed & Shale	1,400
Shale Shells & Sand	1,505
Anhydrite	1,535
Red Bed & Shale	1,650
Lime & Shale	1,995
Shale & Lime	2,100
Lime & Shale	2,480
Shale & Lime	2,535
Ft Riley	2,535
Lime & Shale	2,770
Lime broken	2,890
Shale & Lime	3,040
Lime & Shale	3,180
Lime	3,250
Lime & Shale	3,362
Lime	3,418
Lime & Shale	3,455
Lime	3,475
Lime & Shale	3,570
Lime	3,611
Lime & Shale	3,645
Lime - Arbuckle	3,672 Rotary T.D.

RECEIVED
 STATE COMMISSION

NOV 22 1961

CONSERVATION DIVISION
 Wichita, Kansas

The undersigned, Richard A. Shelley, Partner of Shelley-Miller Drilling Company, hereby certifies in behalf of said company, that the above log is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

SHELLEY-MILLER DRILLING COMPANY

By Richard A. Shelley

STATE OF KANSAS)
 COUNTY OF SEDGWICK) SS

BE IT REMEMBERED, that on this 21st day of November, 1961, before me, the undersigned, a Notary Public, duly commissioned in and for the county and state aforesaid, came Richard A. Shelley, Partner, and known to me to be the same person who executed the foregoing instrument of writing in behalf of Shelley-Miller Drilling Company, as a Partner of said Company, and he duly acknowledged the execution of the same for himself and for said Company.

IN WITNESS WHEREOF, I have hereunto set my hand and official seal on the day and year last above written.

Leona M. Powers
 Notary Public

My Commission Expires:
 March 24, 1964