

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Ellis County, Sec. 32 Twp. 11S Rge. (E) 18 (W)  
Location as "NE/CNW/SW" or footage from lines NW NW NW  
Lease Owner Shell Oil Company  
Lease Name Johnson "C" Well No. 1  
Office Address 1200 First National Building  
Character of Well (completed as Oil, Gas or Dry Hole) Oil  
Date well completed October 19 64  
Application for plugging filed August 7 19 64  
Application for plugging approved August 11 19 64  
Plugging commenced 19  
Plugging completed September 3 19 64  
Reason for abandonment of well or producing formation Depleted

NORTH

X			

Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production July 5 19 64  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Eldon Petty  
Producing formation Arbuckle Depth to top 3485 Bottom 3596 Total Depth of Well 3596 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Arbuckle	Oil	3485	3596	8	1500	NONE
				5-1/2	3591	2333

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Plug back to 3300' with sand and capped with 4 sacks cement.

Pulled pipe to 550' circ. mud. Spotted 20 sacks cement.

Plug at 550'. Spotted 20 sacks cement plug at 200'.

Capped surface with 10 sacks cement.

37...  
SEP 18 1964  
...

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Shell Oil Company  
Address 1200 First National Building Oklahoma City, Oklahoma 73102

STATE OF Oklahoma, COUNTY OF Oklahoma, ss.  
C. A. Wischoff (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. A. Wischoff  
1200 First National Bldg. Okla. City, Okla. 73102  
(Address)

SUBSCRIBED AND SWORN to before me this 17th day of September, 19 64

My commission expires Jan. 19, 1968

[Signature] Notary Public.



Well Log

Shell Oil Company  
 Johnson "C" No. 1  
 NW NW NW Section 32-11S-18W  
 Riverview Field  
 Ellis County, Kansas

Casing Record

8" casing set @ 1500 ft.  
 5-1/2" casing set @ 3200 ft.

NOTE: The above well was purchased from Champlin Oil Company in March, 1962.  
 The only available log is from 2900 ft. to total depth.

Formation

2900-2906	Shale	3144-3160	Shale & lime
2906-2916	Limestone	3160-3202	Lime
2916-2921	Shale	3202-3206	Shale
2921-2934	Limestone	3206-3270	Lime
2934-2941	Shale	3270-3274	Shale
2941-2958	Limestone	3274-3278	Lime
2958-2970	Shale	3278-3290	Shale
2970-2983	Limestone	3290-3304	Lime
2983-2988	Shale	3304-3312	Shale
2988-2991	Lime	3312-3334	Lime
2991-3012	Shale & lime	3334-3343	Shale
3012-3018	Lime	3343-3434	Lime
3018-3022	Shale	3434-3446	Shale
3022-3027	Lime	3446-3462	Lime
3027-3030	Shale	3462-3468	Shale
3030-3034	Lime	3468-3498	Lime
3034-3045	Shale	3498-3505	Shale
3045-3069	Lime	3505-3530	Lime
3069-3071	Shale	3530-3534	Shale
3071-3087	Lime	3534-3542	Lime
3087-3090	Shale	3542-3562	Lime & shale
3090-3093	Lime	3562-3572	Lime
3093-3097	Shale	3572-3585	Shale
3097-3144	Lime	3585-3596	Limestone
		3596	TOTAL DEPTH

**RECEIVED**  
 STATE CORPORATION COMMISSION

AUG 11 1964

CONSERVATION DIVISION  
 Wichita, Kansas