

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.--82-3-117

API NUMBER 15051013330002

LEASE NAME Johnson Z

WELL NUMBER #1

 Ft. from S Section Line

 Ft. from E Section Line
SE SW SW

SEC. 32TWP. 11SRGE. 18W (E)or(W)

COUNTY Ellis

Date Well Completed

Plugging Commenced 6-16-87

Plugging Completed 6-16-87

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Hummon Corporation

ADDRESS 400 One Main Place
Wichita, Kansas 67202

PHONE#(316) 263-8521 OPERATORS LICENSE NO. 5050

Character of Well Inj.

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? Yes

Which KCC Office did you notify? Dist. #6 Hays, Kansas

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 3606½

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	363'	none
				5-1/2"	3606½	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Plug Job Only-No Pipe Recovery: Pumped 5 sacks hulls and 280 sacks econolite down 5-1/2" casing and 20 sacks econolite down backside.

Plugging Complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling, Inc. License No. 6050

Address P.O. Box 347 Chase, Kansas 67524 STATE CORP. COMMISSION

STATE OF Kansas COUNTY OF Rice, ss. JUN 19 1987

Mike Kelso, Vice-President

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) Mike Kelso

(Address) P.O. Box 347 Chase, Kansas 67524

SUBSCRIBED AND SWORN TO before me this 18th day of June, 19 87

James Hoover
Notary Public

My Commission Expires:



DRILLERS LOG

Johnson "Z" #1

Loc: C-SE SW SW
Sec: 32-11S-18W
Ellis County, Kansas
Operator: Cooperative Refinery Ass'n.
Contractor: Shields Drilling Company

Elevation: 2046 R.B.
Casings: 8 5/8" at 363' w/ 175 ex.
5 1/2" at 3606 1/2 w/ 125 ex.
Comms: 11-3-56 Comp: 11-17-56
R.T.D.: 3608

<u>From</u>	<u>To</u>	<u>Formation</u>
0	25	Surface clay
25	175	Sand and shale
175	363	Shale and shells
363	760	Shale
760	1050	Sand
1050	1365	Red bed, shals
1365	1396	Anhydrite
1396	1755	Red bed, shale and shells
1755	1975	Shale and shells
1975	2255	Lime and shale
2255	2345	Lime
2345	2565	Lime and shale
2565	2795	Lime
2795	3060	Lime and shale
3060	3537	Lime
3537	3590	Lime and conglomerate
3590	3608	Lime
3608		R.T.D.

(STATE OF KANSAS)
(COUNTY OF BARTON)

I hereby certify that the above is a true and correct copy of the log on the Johnson "Z" #1 well, located C SE SW SW of Section 32-11S-18W, Ellis County, Kansas.

M. D. Sullivan

Subscribed and sworn to before me this 20 day of November 1956.

Yvonne Adams

My commission expires: September 24, 1960

RECEIVED
STATE CONSERVATION COMMISSION
MAY 21 1987
CONSERVATION DIVISION
Wichita Kansas