


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Ness County, Sec. 23 Twp. 19 Rge. 24 E/W
Location as "NE/CNW $\frac{1}{2}$ SW $\frac{1}{4}$ " or footage from lines _____

C. SE. SW
Lease Owner F & M Oil Co.
Lease Name Boyd #1 Well No. _____
Office Address Russell, Kansas 67665
Character of Well (Completed as Oil, Gas or Dry Hole) _____



Locate well correctly on above
Section Plat

Date Well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 8/4/79 _____ 19____
Plugging completed 8/9/79 _____ 19____
Reason for abandonment of well or producing formation
depleted.

If a producing well is abandoned, date of last production _____ 19____

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Schmidt
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4356
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	287	none
				5 1/2"	4355	2499

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Sanded to 4300' and ran 5 sacks cement. Loaded hole with salt water, shot pipe at 2904', 2725', 2505', pulled 81 joints. Pumped 2 sacks hulls, 10 sacks gel, 60 sacks cement, 5 sacks gel, 1 sack hulls, plug and 80 sacks cement.

PLUGGING COMPLETE.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KELSO CASING PULLING
CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE, ss.
R. DARRELL KELSO (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
CHASE, KANSAS (Address)

SUBSCRIBED AND SWORN TO before me this 15th day of August, 1979

My commission expires _____



[Signature]
Notary Public.

RECEIVED
STATE CORPORATION COMMISSION

AUG 15 1979

CONSERVATION DIVISION
Wichita, Kansas

DRILLERS LOG

BOYD NO. 1 (OWWO)

SURFACE CASING:	OPERATOR: F & M Oil Co.	DESCRIPTION:
8-5/8" @ 287' w/175 sax	CONTRACTOR: Sage Drilling Co.	C SE SW Sec. 23-19S-24W Ness County, Kansas.
TOTAL DEPTH: 4356'	COMMENCED: January 22, 1972	
<i>CTTD 4364</i>	COMPLETED: February 5, 1972	


<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
		Pull 5½" Casing out of hole. Wash hole to 3550', Deviat hole and redrill
3350	3609	Lime
3609	3750	Shale & Lime
3750	3906	Lime & Shale
3906	4356	Lime 5½" set @ 4355' w/225 sax cement

RECEIVED
STATE CORPORATION COMMISSION
JUL 30 1979
DEPARTMENT OF REVENUE
TREASURER

I certify that this is a true and correct copy of our operations on the above captioned well to the best of my knowledge.

SAGE DRILLING CO., INC.

By John R. Bartholomew
John R. Bartholomew



Subscribed and sworn to before me this 11th day of February, 1972.

Louise K. Whitted
Louise K. Whitted, Notary Public

My commission expires:
November 26, 1974.