

K-135-00664-0000

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Ness County, Sec. 3 Twp. 19 Rge. 26W (E) (W)

Location as "NE/CNW/SW" or footage from lines C NE SW

Lease Owner Kern-Landes Exploration Co., Inc.

Lease Name Pember Pember Well No. 1

Office Address Box 107 Liberal, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) D&A

Date well completed Sept. 26 19 63

Application for plugging filed 19

Application for plugging approved 19

Plugging commenced 19

Plugging completed October 2, 19 62

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation Depth to top Bottom Total Depth of Well 4541' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	290'	8 5/8"	290'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

8 5/8" 300' circulated with cement - 4 1/2" 4541' with 250 sacks cement - perf 4417'

Pulled 3000' 4 1/2" to 300', circulated hole with heavy mud, displaced 30 sacks readymix cement through 4 1/2" at 300', heavy mud to 401', set plug, hulls and filled to bottom cellar with readymix cement.

RECEIVED
STATE CORPORATION COMMISSION

OCT 1 1963

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Hellar Drilling Co., Inc.

Address 1014 Union Center Wichita, Kansas

STATE OF Kansas COUNTY OF Sedgwick, ss.

D. L. Hellar, Pres. Hellar Drlg. Co. Inc. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) D. L. Hellar, Pres.

1014 Union Center, Wichita, Kansas

(Address)

SUBSCRIBED AND SWORN TO before me this 30th day of September, 19 63

My commission expires March 25, 1964.

Catherine Darcey Notary Public.

DRILLERS LOG

COMPANY:	Kern-Landes Exploration Co. Inc.
CONTRACTOR:	Hellar Drilling Company, Inc.
LEASE:	#1 Pumber
LOCATION:	c NE SW 3-18-26W Ness County, Kansas
COMMENCED:	September 13, 1962
COMPLETED:	September 26, 1962
CASING:	Set 8 5/8" surface casing @ 290'/175 sacks cement - Set 4 1/2" casing @ 4526'/250 sacks cement

0- 290	Surface sand, Post rock- shells & shale
290- 370	Shale
370-1244	Shale & Shells
1244-1258	Blaine-Anhydrite
1258-1261	Blaine
1261-1820	Sand-Shale-Red Bed
1820-1852	Shale & Red Bed
1852-1890	Cimarron-Anhydrite
1890-2093	Shale, Red Bed
2093-2423	Shale, Red Bed & Salt Section
2423-2763	Shale & Lime
2763-2855	Ft. Riley
2855-3028	Lime & Shale
3028-3461	Shale & Lime
3461-3916	Lime & Shale
3916-3969	Toronto & Lansing-Kansas City
3969-4053	Lime
4053-4136	Lansing-Kansas City
4136-4194	Lime
4194-4228	Lansing-Kansas City
4228-4339	Lime
4339-4420	Lime & Shale
4420-4442	Beam Rat Hole
4442-4449	Lime (Ft. Scott)
4449-4498	Lime, Chalky Lime & Slate
4498-4503	Beam Core Hole
4503-4534	Beam Rat Hole
4534-4543	Mississippi
4543	Rotary Total Depth

RECEIVED
STATE CORPORATION COMMISSION
OCT 1 1962
CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

I, D. L. Hellar, do hereby certify that the above and foregoing is a true and correct copy of the log of the #1 Pumber, located c NE SW 3-18-26W, Ness County, Kansas, as reflected by the files of the Hellar Drilling Company, Inc.

HELLAR DRILLING COMPANY, INC.

By D. L. Hellar
D. L. Hellar, President

Subscribed and sworn to before me, a Notary Public, in and for Sedgwick County, Kansas, this 10th day of October, 1962.

Catherine Harney
Notary Public - Catherine Harney

My Commission Expires: March 25, 1964.