


15-135-00052-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

Ness County. Sec. 3 Twp. 9S Rge. 26 (W)
Location as "NE/CNW&SW" or footage from lines SW/4 SW/4 NW/4
Lease Owner Barnett Oil Company, et al
Lease Name Adolph Well No. 1
Office Address 411 First National Bank Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed September 14, 1956
Application for plugging filed September 14, 1956
Application for plugging approved September 15, 1956
Plugging commenced September 14, 1956
Plugging completed September 14, 1956
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production - - - 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well R. M. Brundege
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4567 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	187 1/2'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with mud; pushed first plug to 810'; cemented through drill pipe by Service Company with 25 sacks; pulled drill pipe and filled hole with mud to 190'; set plug with 1/2 sack hulls on top; cemented through drill pipe with 15 sacks; filled hole with mud to 35'; set plug with 1/2 sack hulls on top; cemented to surface with 10 sacks. Filled rat hole with dry dirt; covered top with cement.

(Well Log attached)

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Barnett Drilling, Inc.
Address 409 First National Bank Building, Wichita, Kansas

STATE OF Kansas COUNTY OF Sedgwick ss.
F. H. Rousey (employee of owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) F. H. Rousey
411 First Nat'l Bank Bldg., Wichita, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 17th day of September, 1956

My commission expires February 27, 1960. Notary Public.

PLUGGING
FILE SEC 3 T. 19. R. 26W
BOOK PAGE 98 LINE 43

09-18-56

K-135-00052-0000

BARNETT OIL COMPANY
WELL LOG - ADOLPH NO. 1
SW/4 SW/4 NW/4 OF SECTION 3-19S-26W
NESS COUNTY, KANSAS

Date Started: 8/31/56
Date Completed: 9/14/56

<u>From</u>	<u>To</u>	<u>Formation</u>
0	20	Surface clay
20	50	Post rock
50	80	Shale and Shells
80	90	Sand
90	100	Shale
100	188	Blue Shale
188	580	Shale
580	665	Sand
665	1320	Shale and Shells
1320	1560	Sand
1560	1860	Shale and Shells
1860	1890	Anhydrite
1890	1940	Shale
1940	2530	Shale and Shells
2530	2660	Shale and Lime
2660	2945	Lime
2945	3275	Lime and Shale
3275	4567	Lime (Total Depth) (D. & A.)

Set 8 5/8" casing at 187½' with 150 sacks
of cement.

PLUGGING			
FILE	SEC. 3	T. 19	R. 26W
BOOK	PAGE 98	LINE	43