

**STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION**

130 S. Market, Room 2078  
Wichita, Kansas 67202

WELL PLUGGING APPLICATION FORM

(PLEASE TYPE FORM and File ONE Copy)

FORM CP-1

Rev. 03/92

**RECEIVED**

**JUN 26 2002**

**KCC WICHITA**

API #: 15-135-24178-00-00 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate sp or completion date

WELL OPERATOR: McCoy Petroleum Corporation

(owner/company name)

KCC LICENSE # 5003

(operator's)

ADDRESS: P. O. Box 780208

CITY: Wichita

STATE: Kansas ZIP CODE 67278-0208

CONTACT PHONE: 316-636-2737

LEASE: Mellies 'B'

WELL#: No. 1-30

Section 30

Township 19s

Range 24w

S/2 Sw Se

SPOT LOCATION/QQQQ

COUNTY: Ness

330 FEET (in exact footage) FROM South LINE OF SECTION (NOT Lease Line)

1980 FEET (in exact footage) FROM East LINE OF SECTION (NOT Lease Line)

**Check One:**

Oil Well

Gas Well

D&A

XX

SWD/ENHR WELL

Docket #

CONDUCTOR CASING SIZE None

SET AT

CEMENTED WITH

SACKS

SURFACE CASING SIZE 8-5/8"

SET AT 535' KB

CEMENTED WITH

275

SACKS

PRODUCTION CASING SIZE None

SET AT

CEMENTED WITH

SACKS

**LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS:**

ELEVATION 2351 G.L.

2360 K.B.

T.D.

4456

PBTD

Anhydrite Depth 1632

(Stone Corral Formation)

CONDITION OF WELL: GOOD XX

POOR

CASING LEAK

JUNK IN HOLE

**PROPOSED METHOD OF PLUGGING:**

Plugging orders received from Steve Middleton at 4:15 pm on 06/18/02. Plugged using 205 sx 60/40 Poz,

6% Gel and 1/4#/sx Flow Seal as follows: Heavy mud in hole, Bottom plug 50 sx @ 1640', 80 sx @ 800',

50 sx @ 550', 10 sx @ 40' cemented to surface. Intervals between plugs are heavy mud. Plugged Rathole

with 15 sx. Job completed at 8:30 pm on 06/20/02 by Allied Cementing. Ticket # 7741.

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED?

Yes (YES,NO)

IS ACO-1 FILED? ? (YES,NO)

If not explain why?

**PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.**

**LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:**

Name: Gary Pugh/Gary M. Talbott

Phone#: (316) 672-9508

Address: P.O. Box 1006

City: Pratt

State: Kansas

PLUGGING CONTRACTOR: Sterling Drilling Company

(company name)

KCC LICENSE #:

5142

(contractor's)

Address: P.O. Box 1006

City: Pratt

State: Kansas

Zip 67124

PROPOSED DATE AND HOUR OF PLUGGING (If Known?)

Plugged well at 8:30 pm on June 20, 2002.

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY:

Operator X Agent

DATE: 06/20/02 AUTHORIZED OPERATOR OR AGENT:

(signature) Gary M. Talbott, Agent for Operator