

15-135-00115-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

WELL PLUGGING RECORD

Ness County, Sec. 9 Twp. 19S Rge. 24 (E) (W)

Location as "NE/CNW/SW" or footage from lines NE NE NE

Lease Owner Hilton Drilling Company, Inc.

Lease Name Schaben Well No. 1

Office Address 2421 Tenth Street, Great Bend, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed June 21, 19 56

Application for plugging filed June 21, 19 56

Application for plugging approved June 22, 19 56

Plugging commenced June 21, 19 56

Plugging completed June 21, 19 56

Reason for abandonment of well or producing formation dry hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well R. M. Brundege

Producing formation Depth to top Bottom Total Depth of Well 4431 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	242	8-5/8"	242	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Put in heavy drilling mud from total depth to 240'
Plugged hole with bottom plug and 1/3 sacks hulls @ 240'
with 20 sacks cement.
Top plug and 1/3 sacks hulls @ 35' with 10 sacks cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Hilton Drilling Company, Inc.

Address Great Bend, Kansas

STATE OF KANSAS COUNTY OF BARTON, ss.
Henry Peacock, Secretary (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Henry Peacock
Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 22nd day of June 19 56

(Signature) Mildred Hobbie
Notary Public.

My commission expires

24-7366-6 3-53-20M

MILDRED HOBBI
MY COMMISSION EXPIRES MARCH 6, 1958

PLUGGING
FILE SEC 9 T 19 R 24W
BOOK PAGE 73 LINE 8

06-26-56

DRILLER'S LOG

COMPANY: Hilton Drilling Company, Inc.
 CONTRACTOR: Hilton Drilling Company, Inc.
 FARM NAME: Schaben No. 1
 COMMENCED: June 7, 1956
 COMPLETED: June 21, 1956

LOCATION: NE NE NE
 Section 9-19S-24W
 Ness County, Kansas

ELEVATION: 2297 D.F.

Casing Used: 8-5/8" set @ 242' w/200 sxs.

Clay and Sand	40
Sand, Shells and Shale	100
Sand and Shale	200
Shale	350
Sand (Quick)	470
Shale and Shells	700
Sand	740
Shale	760
Red Bed	950
Lime	960
Red Bed, Shale and Shells	1060
Sand	1130
Red Bed, Shale and Shells	1305
Shale and Shells	1580
Anhydrite	1615
Shale and Shells	1980
Shale and Lime	2245
Lime	2390
Shale and Lime	2515
Lime	2705
Shale and Lime	2930
Brown Lime	3020
Shale and Lime	3310
Lime	3407
Shale and Lime	3510
Lime	4070
Shale and Lime	4112
Conglomerate Lime	4143
Shale and Lime	4325
Chert	4338
Shale and Chert	4364
Chert, Lime and Shale	4374
Shale and Lime	4414
Lime, Shale and Chert	4431
Total Depth	4431

PLUGGING

FILE SEC 9 T. 19 R. 24W
 BOOK PAGE 13 LINE 8

STATE OF KANSAS)
 COUNTY OF BARTON) SS.

I, the undersigned, being duly sworn on oath, state that the above statement and log are true and a correct record and log of the well drilled at the location above-described.

HILTON DRILLING COMPANY, INC.

Henry P. ...

Subscribed and sworn to before me this 22nd day of June, 1956.

MILDRED HOBBIIE
 MY COMMISSION EXPIRES MARCH 6, 1958

Mildred Hobbie
 Notary Public