

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
311 No. Broadway
Wichita, Kansas

Ness County, Sec. 25 Twp. 19 Rge. 24 (E) (W) x

Location as "NE/CNW/SW" or footage from lines SE SE SE

Lease Owner O. A. Sutton Oil Productions

Lease Name Boyd "A" Well No. #1

Office Address 407 Insurance Bldg., Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole)

Date well completed 19

Application for plugging filed 19

Application for plugging approved 6-2-65 19


Plugging commenced 6-10-65 19

Plugging completed 6-13-65 19

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced?



Name of Conservation Agent who supervised plugging of this well Donald Truan

Producing formation Depth to top Bottom Total Depth of Well 4837' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Made plug back with sand to 4260'. Mixed and ran 4 sacks cement thru dump bailer. Mudded hole to 40' and set 10' rock bridge. Mixed and dumped 10 sacks cement to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION

JUN 15 1965

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Southwest Casing Pulling Co., Inc.
Address Box 364, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
Southwest Casing Pulling Co., Inc. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. C. Spencer, Sec.
Box 364, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 14 day of June, 1965

My commission expires 21 October 1968
Sidney D. Miller
Notary Public.

O. A. SUTTON, BOYD #1
 SE SE SE Sec. 25-19S-24W
 Ness County, Kansas

Commenced - April 24, 1959
 Completed - May 15, 1959
 Casing - 491' of 8-5/8" csg. w/300 sacks HA5 cement
 4450' of 5-1/2" csg. w/200 sacks cement
 Elevation - 2292 KB

DRILLERS LOG

0 - 491	Surface
491 - 915	Shale and red bed
915 - 1360	Shale and red bed
1360 - 1558	Shale and red bed
1558 - 1590	Anhydrite
1590 - 1824	Gyp. and red bed
1824 - 2080	Shale and red bed
2080 - 2280	Shale and lime
2280 - 2400	Lime
2400 - 2511	Lime
2511 - 2620	Lime
2620 - 2690	Lime
2690 - 2760	Lime and shale
2760 - 2845	Lime
2845 - 2975	Lime
2975 - 3250	Lime
3250 - 3330	Lime
3330 - 3475	Lime and chalk
3475 - 3570	Lime and shale
3570 - 3620	Lime and shale
3620 - 3775	Lime
3775 - 3820	Lime
3820 - 3865	Lime, cherty
3865 - 3928	Lime
3928 - 4041	Lime
4041 - 4120	Lime
4120 - 4207	Lime
4207 - 4227	Lime
4227 - 4268	Lime and shale
4268 - 4316	Lime
4316 - 4339	Lime
4339 - 4365	Cong. chert
4365 - 4405	Miss.
4405 - 4440	Miss. lime, cherty
4440 - 4467	Miss. chert
4467 - 4542	Miss.
4542 - 4581	Lime
4581 - 4613	Lime
4613 - 4640	Kinderhook
4640 - 4654	Viola
4654 - 4705	Lime
4705 - 4735	Viola lime and chert
4735 - 4745	Lime
4745 - 4797	Simpson
4797 - 4835	Lime
4835 -	Rotary Total Depth

RECEIVED
 STATE CORPORATION COMMISSION
 JUN 2 1965
 CONSERVATION DIVISION
 Wichita, Kansas

STATE OF KANSAS)
 SEDGWICK COUNTY) ss

I, the undersigned, being duly sworn on oath, state that the above drillers log is true and correct to the best of my knowledge and belief and according to the records of this office.

RENFRO DRILLING CO.

By Henry S. Ficken

Subscribed and sworn to before me this 20th day of May, 1959.

Lorraine Skellcutt
 Notary Public

My commission expires
 June 1, 1960.