

15-135-20475-0000

RECEIVED
STATE CORPORATION COMMISSION


OCT 7 1971

CONSERVATION DIVISION
Wichita, Kansas Form CP-4STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD

NORTH

Locate well correctly on above
Section Plat

Ness County. Sec. 24 Twp. 19S Rge. 24W (E) W (W)
Location as "NE/CNW/SW" or footage from lines C/SW SE
Lease Owner Brandt and Clark Oil Company
Lease Name Boyd Well No. 1
Office Address 505 First National Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) D&A
Date well completed September 20, 1971
Application for plugging filed September 20, 1971
Application for plugging approved September 20, 1971
Plugging commenced September 20, 1971
Plugging completed September 20, 1971
Reason for abandonment of well or producing formation D&A

If a producing well is abandoned, date of last production 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo F. Massey
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4359 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	267'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole w/mud up to 700'
50 sacks cement, mud up to base
of surface pipe 260' set plug
1/2 sx hulls 25 sx cement
set plug 1/2 sx hulls, 10 sx cement
2 sx in rathole.

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Red Tiger Drilling Company
Address 1720 Wichita Plaza Bldg., Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Jim Farrice (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jim Farrice
1720 Wichita Plaza, Wichita, Kansas 67202
(Address)

Subscribed AND SWORN to before me this 6th day of October, 1971

My commission expires July 23, 1974

Notary Public.

DRILLERS LOG

No. 1 Boyd

CASING RECORD:	COMPANY:	Brandt and Clark Oil Company	DESCRIPTION:
8 5/8" @ 267'	CONTRACTOR:	Red Tiger Drilling Company	C/SW SK
w/180 sx cement	COMMENCED:	September 7, 1971	24-19S-24W
	COMPLETED:	September 20, 1971	Ness County, Kansas
TOTAL DEPTH: 4359'			ELEVATION:

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Sod clay & rock	0	250	
Shale	250	269	
Shale & sand	269	720	
Red Bed	720	880	
Shale - Anhy. strks.	880	980	
Sand	980	1200	
Shale & red bed	1200	1525	
Anhydrite	1525	1578	
Shale	1578	2140	
Shale & lime	2140	2535	
Lime	2535	2625	
Lime & shale	2625	3579	
Lime	3579	4344	
Lime & chert	4344	4353	
Chert	4353	4359	

RECEIVED
STATE CORPORATION COMMISSION
OCT 6 1971
CONSERVATION DIVISION
Wichita, Kansas

I certify that this is a true and correct copy of the above log to the best of my knowledge.

RED TIGER DRILLING COMPANY

Jim Farrice
Jim Farrice

Subscribed and sworn to before me this 22nd day of September, 1971.

Virginia K. Albert
Notary Public



My Commission Expires: July 23, 1974

DRILLERS LOG

No. 1 Boyd

CASING RECORD:	COMPANY:	Brandt and Clark Oil Company	DESCRIPTION:
8 5/8" @ 267'	CONTRACTOR:	Red Tiger Drilling Company	C/SW SE
w/180 sx cement	COMMENCED:	September 7, 1971	24-19S-24W
	COMPLETED:	September 20, 1971	Ness County, Kansas
TOTAL DEPTH: 4359'			ELEVATION:

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Sod clay & rock	0	250	
Shale	250	269	
Shale & sand	269	720	
Red Bed	720	880	
Shale - Anhy. strks.	880	980	
Sand	980	1200	
Shale & red bed	1200	1525	
Anhydrite	1525	1578	
Shale	1578	2140	
Shale & lime	2140	2535	
Lime	2535	2625	
Lime & shale	2625	3579	
Lime	3579	4344	
Lime & chert	4344	4353	
Chert	4353	4359	


RECEIVED
STATE CORPORATION COMMISSION
OCT 7 1971
CONSERVATION DIVISION
Wichita, Kansas

I certify that this is a true and correct copy of the above log to the best of my knowledge.

RED TIGER DRILLING COMPANY

Jim Farrice
Jim Farrice

Subscribed and sworn to before me this 22nd day of September, 1971.



Virginia H. Albert
Notary Public