


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

WELL PLUGGING RECORD



Ness County, Sec. 30 Twp. 19 Rge. 24 (W) (W)
Location as "NE/CNW/SW" or footage from lines. NE 1/4 NE 1/4 SW 1/4
Lease Owner Solar Oil Company
Lease Name Schlegel Well No. 1
Office Address 1117 Union Natl. Bldg. Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed April 27, 19 60
Application for plugging filed June 4 19 60
Application for plugging approved June 4 19 60
Plugging commenced June 4 19 60
Plugging completed June 9 19 60
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19 _____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Gilbert Leiker
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4440 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	552'	none
				5 1/2"	4440'	3980'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged off bottom with sand from 4440' to 4260'. Dumped 5 sx. cement from 4260' to 4220'. Pulled 3980' of 5 1/2" casing. Used Sun Oilwell Cementing Company to plug well. Mixed and pumped in 20 sx. of heavy gel-mud, put in plug. Mixed and pumped in 75 sx. cement from 560' to 330'. Filled hole with mud to 20'. Set 5' rock bridge from 20' to 15'. Mixed and put in 5 sx. cement to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION

JUL 7 1960

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Ace Pipe Pulling Company License # 2
Address Box 304 Great Bend, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. B. McFarland
R. B. McFarland

(Address)

SUBSCRIBED AND SWORN TO before me this 10th day of June, 19 60

My commission expires July 27, 1963

Leota Lee Miller
Leota Lee Miller Notary Public.



D R I L L E R S L O G

Company: Solar Oil Company
 Farm: Schlegel #1
 Commenced: April 12, 1960

NE NE SW Section 30-19-24W
 Ness County, Kansas
 Completed: April 28, 1960

Elevation: 2333 KB

0 - 440 shale
 440 - 500 sand & shale
 500 - 700 shale
 700 - 1005 red bed, shale & sand
 1005 - 1040 anhydrite
 1040 - 1100 shale - red bed
 1100 - 1325 sand
 1325 - 1600 shale - lime
 1600 - 2115 lime
 2115 - 2235 lime & shale
 2235 - 2870 lime
 2870 - 3300 lime & shale
 3300 - 3505 lime
 3505 - 3720 lime & chalk
 3720 - 4160 lime
 4160 - 4312 lime & shale
 4312 - 4370 lime, shale & sand
 4370 - 4380 lime & shale
 4380 - 4407 Mississippian
 4407 - 4440 Miss.-lime & chert
 4440 total depth

RECEIVED
 STATE CORPORATE COMMISSION

JUL 7 1960

CONSERVATION DIVISION
 Wichita, Kansas

Set 552 feet of 8 5/8" surface pipe. Cemented with 235 sacks of cement with 2% calcium chloride & 2% Gel. Cement circulated.

Tops: Anhydrite - 1005'
 Heebner - 3732'
 Mississippian - 4380'

Drill Stem Tests: #1 4290-4312 Shut in 20 min. Open 40 min. Shut in 20 min.
 Recovered 900' gas. 90' frothy oil & gas cut mud.
 Initial BHP - 1220# FBHP-1100# IFP-25# FFP-50#
 #2 4385-4392 Shut in 20 min. Open 20 min. Shut in 20 min.
 Recovered 6' mud. Initial BHP-25# FBHP-0#
 IFP-0# FFP-25#
 #3 4393-4407 Shut in 20 Min. Open 30 Min. Shut in 20 min.
 Recovered 5' mud.

Ran electric log.
 Ran 4393 feet of 5 1/2" casing.


A F F I D A V I T

STATE OF KANSAS)
)SS
 County of BARTON)

I, Allan Harms of the Harms-Burt Drilling Company being first duly sworn on oath state:
 I have knowledge of the facts, statements and matters herein contained and the same are
 true and correct.

Subscribed and sworn to before me this 10 day of May, 1960

My commission expires January 20, 1962.


 Mary E. Van Pelt
 Notary Public