

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
JAN 21 1972
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Hyde & Bitler

Complete Address Box 8316 Prairie Village, Kansas 66208

Lease Name H. Fischer Well No. 1

Location NW NW Sec. 15 Twp. 19 Rge. (E) (W) 24

County Ness Total Depth 4420'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Pipe Pullers, Inc.

Address Box 486 Ellinwood, Kansas 67526 License No. 462

Operation Completed: Hour 10:30 A Day 19 Month 1 Year 1972

The above well was plugged as follows:

Total Depth 4420' 8 5/8 csg set at 284' cwc

5 1/2 csg set at 4415' cw 175 sk cmt.

Filled 5 1/2 csg W/sd (4380-4420) Dumped 5 sk cmt W/dump bailer. (434504380)

Cutoff and recovered 2530' of 5 1/2 csg.

Pumped down 8 5/8 csg with 20 sk gel & water W/300 lbs hulls, -60 sk 50-50 poz cmt

6% gel, -5 sk gel & water, -released plug and pumped 60 sk 50-50 poz cmt 6% gel.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo I. Massey
Well Plugging Supervisor

DATE 1-21-72
INV. NO. 5049-W