

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION
DEC 2 1974
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name F & M Oil Co., Inc.
Complete Address 603 Union Center, Wichita, Kansas
Lease Name Davison Well No. 1
Location SW SE Sec. 9 Twp. 19 Rge. (E) (W) 24
County Ness Total Depth 4385'
Abandoned Oil Well Gas Well Input Well SWD Well D & A XX
Other well as hereafter indicated
Plugging Contractor H-30 Drlg.
Address Wichita, Kansas License No.
Operation Completed: Hour 7:20 A Day 1 Month 12 Year 1974

The above well was plugged as follows:

RTD 4385' 8 5/8 csg set at 208' cwc 150 sx. Plg. Mat. 50-50 poz 6% total gel.
Gunned pits, circulated heavy mud, set 70 sk cmt plug at 550' thru drill pipe.
Heavy mud to 185' & set 20 sk cmt plug thru drill pipe. Heavy mud to 40' set
cementing plug, 1/2 sk hulls and 10 sx cmt to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Lewis Brock
Well Plugging Supervisor

DATE 12/4/74
INV. NO. 404-w