

P

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

RECEIVED
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

MAR 22 1978

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15-135-20598-0000 (of this well)

Operator's Full Name Mull Drilling Co., Inc.

Complete Address 415 Page Ct.-220 W. Douglas, Wichita, Kansas 67202

Lease Name Miner "A" Well No. 1

Location C SE SW Sec. 9 Twp. 19 Rge. (E) (W) 24

County Ness Total Depth 4376'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Rockhold Engineering, Inc.

Address Box 698 Great Bend, Kansas License No. 670

Operation Completed: Hour 10 A Day 21 Month 3 Year 1978

The above well was plugged as follows:

Total Depth 4376' 8 5/8 csg set 205' cwc 150 sk.

5 1/2 csg set 4369' cw 150 sk cem.

Filled 5 1/2 csg W/sd (4376'-4350') dumped 5 sk cem. W/dump bailer. (4350'-4315')

Cutoff & recovered 3200' of 5 1/2 csg.

Halliburton Cementing Co. mixed & pumped down 8 5/8 csg with 20 sk gel & water

W/100 lbs hulls -followed with 70 sk 50-50 poz 2% -displaced with 6 sk gel & water-

released 8 5/8 cementing plug & capped with 70 sk 50-50 poz 2% & shutin. FPP 500 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 3-23-78

Signed: Leo Messerly
Well Plugging Supervisor

6983-W