

15-135-20265-0000

Form CP-3
Rev. 6-4-68

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JUL 18 1969
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Atward Drilling Co.

Complete Address 909 1st Nat'l Bank Bldg.,

Lease Name Boyd Well No. 1

Location NW SE Sec. 25 Twp. 19 Rge. (E) (W) 24

County Ness Total Depth 4430

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Red Tiger Drlg.

Address Wichita, Kansas License No.

Operation Completed: Hour 12:30P Day 14 Month 7 Year 1969

The above well was plugged as follows:

RTD 4430' 8 5/8 csg set at 490' cwc Cmt Mat 50-50 poz cmt W/6% total gel.

Gunned pits, circulated heavy mud, set cementing plug at 660' and displaced 50 sk cmt

thru drill pipe. Heavy mud to 480' set cementing plug and displaced 25 sk cmt thru

drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to base

of cellar. Plugged rat hole with 2 sk cmt.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 7/18/69
INV. NO. 118-W

Signed: Red T. Massey
Well Plugging Supervisor