

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

JUN 21 1965

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name O. A. Sutton

Complete Address: 407 Insurance Bldg Wichita, Kans

Lease Name Boyd Well No. A-1

Location SE SE SE Sec. 25 Twp. 19 Rge. (E) (W) 24

County Ness Total Depth 483'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Southwest Casing Pulling

Address: Great Bend, Kans License No. _____

Operation Completed: Hour 5PM Day 13 Month 6 Year 65

The Above well was plugged as follows:

8 5/8" 491' circulated with cement - 5 1/2" 4450' with 200 sax cement
Sand to 4200', set 4 sax cement with dump bailer - pulled 2005' 5 1/2"
to 600' circulated hole with heavy mud through 5 1/2" at 600' - pulled pipe to
480', spotted 25 sax cement through 5 1/2" at 480', heavy mud to 215', displaced
20 sax cement through 5 1/2" at 215', heavy mud to 35', set bridge and 10 sax
cement to bottom cellar.

Mudding and cementing by Southwest Company pump truck.

I hereby certify that the above well was plugged as herein stated.

DATE 6/22/65
INV. NO. 1341-W

Signed: Eldon Petty
Well Plugging Supervisor