

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202RECEIVED
STATE CORPORATION COMMISSION
SEP 28 1971
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Brandt & Clark

Complete Address 505 First National Bank Wichita, Kansas

Lease Name Boyd Well No. 1

Location C SW SE Sec. 24 Twp. 19 Rge. (E) (W) 24

County Ness Total Depth 4359'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Red Tiger Drlg.

Address Wichita, Kansas License No.

Operation Completed: Hour 8:30 P Day 20 Month 9 Year 1971

The above well was plugged as follows:

RTD 4359' 8 5/8 csg set at 267' cwc Cmt. Mat. cement cmt(Sacks)

Gunned pits, circulated heavy mud, set cementing plug at 720' and displaced 50 sk cmt thru drill pipe. Heavy mud to 260' set cementing plug and displaced 25 sk cmt thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to base of collar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Wesley J. [Signature]
Well Plugging SupervisorDATE 9-29-71INV. NO. 4390-112