

15-135-20209-0000

Form CP-3
Rev. 6-26-62

KANSAS

Handwritten mark

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
NOV 22 1968
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Pickrell Drilling Company
Complete Address: 705 4th Nat'l Bank Bldg., Wichita, Kansas
Lease Name Shramek "AW" Well No. 1
Location C NW SE Sec. 32 Twp. 19 Rge. 24 (E) (W) XX
County Ness Total Depth 4450
Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D & A XX
Other well as hereafter indicated: _____
Plugging Contractor: Co. Tools
Address: _____ License No. _____
Operation Completed: Hour 6:15A Day 20 Month 11 Year 1968

The Above well was plugged as follows:

RTD 4450' 8 5/8 csg at 255' cwc Cmt. Mat. 50-50 poz cmt. W/6% total gel.
Gunned pits, circulated heavy mud, set cementing plug at 660' and displaced 70 sc cmt.
thru drill pipe. Heavy mud to 240' set cementing plug and displaced 20 sc cement thru
drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and 10 sc cement to base
of cellar. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 11/22/68
INV. NO. 8864-W

Signed: Geo F. Massey
Well Plugging Supervisor