

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION
NOV 26 1973
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Petroleum, Inc.

Complete Address 300 W. Douglas, Wichita, Kansas

Lease Name Rothe "E" Well No. 1

Location C SE NW Sec. 36 Twp. 19 Rge. (E) (W) 24

County Ness Total Depth 4425'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Damco Drlg.

Address Wichita, Kansas License No.

Operation Completed: Hour 5:15 P Day 23 Month 11 Year 1973

The above well was plugged as follows:

RTD 4425' 8 5/8 csg set at 564' cwc 300 sk.

Gunned pits, circulated heavy mud, set cementing plug at 600' and displaced 50 sk
cmt thru drill pipe. Heavy mud to 240' set cementing plug and displaced 25 sk cmt
thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to
base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 11/29/73

INV. NO. 8204-W

Signed: Leo Z. Massey
Well Plugging Supervisor