

15-135-20753-0000

Form CP-3
Rev. 6-26-62



KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
MAY 26 1969
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name McClure Oil Co. & Petroleum Inc.

Complete Address: 1301 Plaza Bldg., Wichita, Kansas

Lease Name Boyd "E" Well No. 1

Location C NW NE Sec. 35 Twp. 19 Rge. (E) (W) 24

County Ness Total Depth 4460

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated:

Plugging Contractor: Rains & Williamson

Address: Wichita, Kansas License No.

Operation Completed: Hour 11:05P Day 24 Month 5 Year 1969

The Above well was plugged as follows:

RTD 4460' 8 5/8 csg set at 496' cwc 325 sk. Cmt. Mat. 50-50 poz 6% gel.

Gunned pits, circulated heavy mud, set cementing plug at 720' and displace 50 sk cmt.

thru drill pipe. Heavy mud to 480' set cementing plug and displace 25 sk cmt thru

drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to base

of cellar. Plugged rat hole with 2 sk cmt.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Geo F. Massey
Well Plugging Supervisor

DATE 5/27/69

INV. NO. 9841-W