

KANSAS

FORM CP-3
Rev. 1-8-82

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-

RECEIVED
STATE CORPORATION COMMISSION
OCT 26 1982

273.0000
Wichita, Kansas

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name Petroleum Energy Inc

Complete Address 710 One-Twenty Bldg - Wichita, KS 67202

Lease Name Jasaway Well No. 1

Location N41-N41-N41 Sec. 6 Twp. 11 Rge. 18 (East)(West)

County Ellis Total Depth 3552

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor Barlow Well Service

Address Mt. Bend, Kansas License No. 981

Operation Completed: Hour: 5:30pm Day: 7 Month: 9 Year: 1982

Plugging Operations attended by Agent?: All Part None

The above well was plugged as follows:

8 5/8" @ 246' w/175 sx - 4 1/2" @ 3551' w/120 sx
BP @ 3300' - Perfs. @ 3276-80' - PB 5 sx cmt
to 3225' - Shut-off @ 2900' + recovered -
Water-flow 2" stream - Pumped 14 sx gel @ 2900 to shut off
water - pulled csg. to 2600" (water-flow) - pumped 25 gel 425
wt. mud to shut-off water: pulled to 1500' pumped
120 sx cmt - pulled to 700' pumped 40 sx. cmt. - pulled to
260' pumped 20 sx cmt - pulled to 40' pumped 10 sx cmt - (all
cmt plugs have mud laden fluid between them).

Amount of Surface Casing: 246'

I hereby certify that the above plugging instructions were given as herein stated.

Signed: Dennis L. Hamel
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

INVOICED

Signed: _____
Conservation Division Agent

DATE 11-15-82
INV. NO. 1617-W