



KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 8 1968  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Glen Rupe

Complete Address: 222 Brown Bldg., Wichita, Kansas

Lease Name Frisbie Well No. 1

Location SW NE NW Sec. 7 Twp. 11 Rge. 18 (E)    (W) X

County Ellis Total Depth 3583

Abandoned Oil Well    Gas Well    Input Well    SWD Well    D & A X

Other well as hereafter indicated:   

Plugging Contractor: Leben Drlg.

Address: Wichita, Kansas License No.   

Operation Completed: Hour 9:30 A Day 4 Month 5 Year 1968

The Above well was plugged as follows:

RTD 3583' 8 5/8 csg set at 208' cwc. Cem. Mat. 100 sc 6% 50-50 poz cem. (145 cu. Ft.)

Gunned pits, circulated heavy mud, set cementing plug at 800' and displaced 70 sc cem.

thru drill pipe. Heavy mud to 200' set cementing plug and displaced 20 sc cement thru

drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and 10 sc cement to base

of cellar. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo F. Mansup  
Well Plugging Supervisor

DATE 5/8/68  
INV. NO. 7716-u