

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 31 1969  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Vincent Oil Corp.  
Complete Address 625 Union Center Bldg., Wichita, Kansas  
Lease Name Madden Well No. 1  
Location SE SW SE Sec. 16 Twp. 11 Rge. (E) (W) 18  
County Ellis Total Depth 3459'  
Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A XX  
Other well as hereafter indicated       
Plugging Contractor Gabbert & Jones  
Address Wichita, Kansas License No.       
Operation Completed: Hour 2:30A Day 29 Month 12 Year 1969

The above well was plugged as follows:  
RTD 3459' 8 5/8 csg set at 217' cwc Cmt. Mat. 50-50 poz 6% gel.  
Gurd/pits, circulate heavy mud, set cementing plug at 500' and displaced 70 sk cmt  
thru drill pipe. Heavy mud to 210' set cementing plug and displaced 20 sk cmt thru  
drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to base  
of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Geo A. Massey  
Well Plugging Supervisor

RECORDED  
DATE 12/31/69  
INV. NO. 1182-W