

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg.

212 N. Market

WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Buffington of Red Tiger Drlg. has this
date requested permission to plug the following described well:

Mr. Buffington guarantees payment of the plugging fee.

Operator's full Name: Brandt & Clark

Complete Address: 505 First Nat'l Bk. Wichita, Ks.

Lease Name: Boyd Well No. 1

Location: C SW SE Sec. 24 Twp. 19 Rge. (E)(W) 24

County: Ness Total Depth 4359' Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Buffington was instructed to plug the well as follows:
Guu pits, circulate heavy mud, set cementing plug at 720' and displace
50 sk cmt thru drill pipe. Heavy mud to 260' set cementing plug and
displace 25 sk cmt thru drill pipe. Heavy mud to 40' set cementing
plug, 1/2 sk hulls and 10 sk cmt to base of cellar.

Very truly yours,

Leo H. Messing
Conservation Division Agent