

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027 3830 S. Meridian  
WICHITA, KANSAS 67217

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 17 1974  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Harold Cain of Strata Drq. Inc. has this date requested permission to plug the following described well:

Mr. Cain guarantees payment of the plugging fee.

Operator's full Name: Thunderbird Drq. Inc.

Complete Address: 7701 E. Kellogg Wichita Ks.

Lease Name: Harkness Well No. A-1

Location: C NW NW Sec. 32 Twp. 19 Rge. 24 (B) (W)

County: Ness Total Depth 4425 Oil Well

Gas Well  Input Well  SWD Well  D & A Lost Hole

Mr. Cain was instructed to plug the well as follows:

pump down Drill stem  
70 sacks cement 50/50 pozmix 6% gel @ 800'  
20 " " " " " @ 320'  
1/2 sack Hulls & wooden plug @ 40'  
Fill to cellar w/ 10 sacks cement 50/50 pozmix 6% gel.

Allied pump. Truck.

Very truly yours,

Walter Balch  
Conservation Division Agent