



# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

### VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 31 1969  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Ehrlich of Murfin Drlg. has this

date requested permission to plug the following described well:

Mr. Ehrlich guarantees payment of the plugging fee.

Operator's full Name: Vincent Oil Corp.

Complete Address: 625 Union Center Bldg., Wichita, Ks.

Lease Name: Madden Well No. 1

Location: SE SW SE Sec. 16 Twp. 11 Rge. (E)(W) 18

County: Ellis Total Depth 3459' Oil Well     

Gas Well      Input Well      SWD Well      D & A XX Lost Hole     

Mr. Ehrlich was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 500' and displace

70 sk cmt thru drill pipe. Heavy mud to 270' set cementing plug and

displace 20 sk cmt thru drill pipe. Heavy mud to 40' set cementing

plug, 1/2 sk hulls and 10 sk cmt to base of cellar.

Very truly yours,

Ben H. Massey  
Conservation Division Agent