

STATE OF KANSAS
KANSAS CORPORATION COMMISSION
CONSERVATION DIVISION
130 South Market - Room 2078
Wichita, Kansas 67202

FORM CP-1 (3/92)

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File ONE Copy)

API # 15-109-20,586.0000 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR Castle Resources, Inc. KCC LICENSE # 9860
(owner/company name) (operator's)

ADDRESS 1000 E 27th, #C CITY Hays

STATE Kansas ZIP CODE 67601-212 CONTACT PHONE # (316) 262-1841

LEASE Ahrens WELL# 2 SEC. 33 T. 12S R. 33 (~~XXX~~/West)

C - NW/4 - SPOT LOCATION/Q000 COUNTY Logan

1320 FEET (in exact footage) FROM S (N) (circle one) LINE OF SECTION (NOT Lease Line)

1320 FEET (in exact footage) FROM E (W) (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL GAS WELL D&A SWD/ENHR WELL DOCKET# _____

CONDUCTOR CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS

SURFACE CASING SIZE 8 5/8" SET AT 314.06' CEMENTED WITH 190 SACKS

PRODUCTION CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: _____

ELEVATION 3133'/3138/ T.D. 4775' PBSD _____ ANHYDRITE DEPTH 2607'-2631'
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Fill w/heavy mud, 1st plug @ 2620' w/25 sks, 2nd plug @ 1518' w/100 sks, 3rd plug @ 365' w/40 sks, 4th plug @ 40' w/10 sks, 15 sks rathole.

Total 190 sks 60/40 posmix, 6% gel, with 1/2# Floseal per sk.
(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? _____ IS ACO-1 FILED? _____

If not explain why? Sent to operator to complete & return

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Tony Martin PHONE# (316) 262-1841

ADDRESS 150 N. Main, Suite 801 City/State Wichita, Ks, 67202

PLUGGING CONTRACTOR Abercrombie RTD, Inc. KCC LICENSE # 30684
(company name) (contractor's)

ADDRESS 150 N. Main, Ste 801, Wichita, Ks, 67202 PHONE # (316) 262-1841 APR 2, 1995

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) 04-23-95 3:30 p.m. 4-28-95

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 04-24-95 AUTHORIZED OPERATOR/AGENT: Justin K. Wharton
(signature) Vice President