

To: 1 071144 4-7
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 135-23,740-000020 R
SW SE SW , SEC. 24 , 'T 19 S, R 24 W/E
330 feet from S section line
3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5123
Operator: Pickrell Drilling Company, Inc.
Name &
Address 110 N. Market, Ste. 205
Wichita, KS 67202

Lease Name Shramek Trust "F" Well # 1
County Ness 141.24
Well Total Depth 4346 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 262

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X
Other well as hereinafter indicated _____

Plugging Contractor Pickrell Drilling Company, Inc. License Number 5123
Address 110 N. Market, Ste. 205, Wichita, KS 67202

Company to plug at: Hour: 12 p.m. Day: 7 Month: 4 Year: 19 93

Plugging proposal received from Doyle Folkerts
(company name) Pickrell Drilling Company, Inc. (phone) 316-262-8427

work: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1541'
1st plug at 1560' with 50 sx cement, 2nd plug at 800' with 80 sx cement,
3rd plug at 450' with 50 sx cement, 4th plug at 290' with 50 sx cement,
5th plug at 40' with 10 sx cement,
6th plug to circulate rathole with 15 sx cement.

_____ Plugging Proposal Received by _____ (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 2:30 p.m. Day: 7 Month: 4 Year: 19 93

ACTUAL PLUGGING REPORT 1st plug at 1560' with 50 sx cement,
2nd plug at 800' with 80 sx cement,
3rd plug at 450' with 50 sx cement,
4th plug at 290' with 50 sx cement,
5th plug at 40' with 10 sx cement,
6th plug to circulate rathole with 15 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
APR 12 1993
CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel 1/2# floseal by Allied.
(If additional description is necessary, use BACK of this form.)

INVOICED
I (did / did not) observe this plugging.
DATE 4-22-93
INV. NO. 37605

Signed Dan Hodson
(TECHNICIAN)

EFFECTIVE DATE: 3-30-93

DISTRICT # 1

SEAT Yes To

State of Kansas
NOTICE OF INTENTION TO DRILL

135-23,740-0000

FORM MUST BE TYPED
FORM MUST BE SIGNED
ALL BLANKS MUST BE FILLED

Must be approved by the K.G.S. five (5) days prior to commencing well

Expected Spud Date 3 - 25 - 93
month day year

OPERATOR: License # 5123 ✓
Name: Pickrell Drilling Company, Inc.
Address: 110 N. Market, Suite 205
City/State/Zip: Wichita, Kansas 67202
Contact Person: Don Beauchamp
Phone: 316-262-8427

CONTRACTOR: License # 5123 ✓
Name: Company Tools

Well Drilled For: Well Class: Type Equipment:
X Oil ... Enh Rec ... Infield ..X Mud Rotary
... Gas ... Storage ... Pool Ext. ... Air Rotary
... OUVO ... Disposal ..X Wildcat ... Cable
... Seismic: ... # of Holes ... Other
... Other

If OUVO: old well information as follows:
Operator:
Well Name:
Comp. Date: ... Old Total Depth

Directional, Deviated or Horizontal wellbore? ... yes ..X.. no
If yes, true vertical depth:
Bottom Hole Location:

Exp. 9/25/93

AFFIDAVIT

200' Alt. II Req.

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.G.S. ...

Pusher Boyle
SPUD DATE 3-29-93 INIT. JLS
LENGTH SURFACE PLANNED 262
RESERVE PIT STATUS- REMOVE FLUID LINED
after salt sect. bbls. when done bbls.
RATHOLED AHEAD? Y N SIZE HOLE
SURFACE PIPE 8 5/8 @ 262 CONDUCTOR
ANHYDRITE T- B-154/ ELEVATION
TD 4346 FORMATION
RAN PIPE @ DV TOOL ALT II DONE
SX Y N
Arbuckle Plug @ Ft. W/ SX
Hug./Council @ Ft. W/ SX
Anhydrite Base @ 1560 Ft. W/ 50 SX
1/2 Base Anyh. @ 800 Ft. W/ 80 SX
1/2, 1/2 Plug @ 450 Ft. W/ 50 SX
Bottom Surface @ 290 Ft. W/ 50 SX
40' Plug @ 40 Ft. W/ 10 SX
RAT HOLE CIRC/W 15 SX MOUSE HOLE W/ SX
WATER WELL, SX (Irr. Well Pond Hauling)
TECHNICIAN SM DATE 4-6-93
TYPE OF CEMENT 60/40 6 1/4 Flo sand
STARTING TIME 2: PM (AM/PM) DATE 4-7-93
COMPLETION TIME 2:30 (AM/PM) DATE 4-7-93
CEMENT COMPANY Colwell
RECEIVED
APR 11 1993
KANSAS DIVISION
WICHITA