

1 090277

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-135-22,722-0000
C SE NW, SEC. 29, T 19 S, R 24 W/E

TECHNICIAN'S PLUGGING REPORT

3300 feet from N/S section line
3300 feet from W/E section line

Operator License # 6009

Lease Name Mellies Well # 1

Operator: Double Eagle Exploration, Inc.
Name & Address 100 S. Main, Suite 410
Wichita, KS 67202

County Ness 143.04

Well Total Depth 4401 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 530 ✓

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Rains & Williamson Oil Co., Inc. License Number 5146

Address 435 Page Court, 220 W. Douglas, Wichita, KS 67202

Company to plug at: Hour: 2:00 pm Day: 21 Month: January Year: 19 85

Plugging proposal received from Bob Klotz

(company name) Rains & Williamson (phone) 316-265-9686

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 1560' with 50 sx cement

2nd plug at ^{solid bridge} 750' with 80 sx cement

3rd plug hulls - plug at 40' -- cement to surface with 10 sx cement

5th plug to circulate rat hole with 15 sx cement

Plugging Proposal Received by Robert Tarbutton
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 3:15 pm Day: 21 Month: January Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 1560' with 50 sx cement, 2nd plug at 750' with 80
sx cement, 3rd & 4th plugs - solid bridge - hulls - plug at 40' -- cement to surface
with 10 sx cement, 5th plug to circulate rat hole with 15 sx cement.

STATE CORPORATION COMMISSION

JAN 23 1985

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Halliburton
(if additional description is necessary, use BACK of this form.)

I (XXX, / did, not) observe this plugging.

Signed Robert Tarbutton
(TECHNICIAN)

1-29-85
6719