

6060070

N-A ✓

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15

NE, Sec. 6, T 11 S, R 18 W

330 feet from N/E section line

330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6273

Lease Name Peavey C Well # 2

Operator: Robert R. Price Operating, Inc.

County Ellis

Name & Address P.O. Box 45442

Well Total Depth 3679 feet \$ 119.57

Tulsa, Ok. 74145

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8" feet 206'

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 176, Chase, Mo. 64524

Company to plug at: Hour: 10:30 AM Day: 16 Month: Nov Year: 1983

VERBAL PLUGGING ORDERS GIVEN TO Michael Kelso

(company name) Kelso Casing Pulling (phone) 316-938-2457

were: Order 165 lbs 50 points - 4 1/2" bit - 7 9/16" O.D., 5 sh. hells, 80 sh. Gel. & 8 5/8" plug.

Signed [Signature]
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 1:00 PM Day: 16 Month: Nov Year: 1983

ACTUAL PLUGGING REPORT 8 5/8" - 206' w/ 175 sh. 5 1/2" - set at 3678' w/ 200 sh.

Plug back TD, 3677'. Top perforat 3222'. Plug bottom w/ 5 sh. cement sand & 5 sh. cement to 3175'. Shot pipe 4 times & removed 12504'. Pumped in 8 5/8" - 4 sh. hells, 25 sh. cement, 15 sh. Gel, 70 sh. cement, 5 sh. Gel, 1 sh. hells, released plug & followed w/ 70 sh. cement w/ 500 pounds pressure.

Remarks: By Sun Cementing

I hereby certify that the above plugging instructions were given as herein stated and that I (did / ~~did not~~) observe this plugging.

INVOICED
DATE 12-27-83
INV. NO. 7214-W

NOV 28 1983

Signed [Signature]
(TECHNICIAN)