

6-10

4-031826

E-23,474 20606-0002

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

AND ICC

API number: 15-051-20,605
~~SW SE SE~~ /4 SEC. 17, 11 S, 18 W
330 feet from S section line
990 feet from E section line

Operator license# 6273 Lease Frisbie well # H-2

Operator: Robert R. Price Operating, Inc. County Ellis

Address: Box 470442 Well total depth 3580 feet ^{116.35}
Tulsa, Oklahoma 74147 Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 250 feet

Aband. oil well , Gas well , Input well X, SWD , D & A

Plugging contractor: Allied Cement Company License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: P.M. Day: 10 Month: June Year: 93

Plugging proposal received from: Price

Company: Robert R. Price Operating, Inc. Phone:

Were: Order 400 sxs. 65/35 pozmix - 10% gel.
Packer on 3" fiberglass sanded in to 1900'. Shot off @ 1875'
with hole on vacuum. Holes in casing.

Plugging Proposal Received by: Carl Goodrow
Plugging operations attended by agent? All[X], Part[], None[]

Completed: Hour: 1:00P.M., Day: 10, Month: June, Year: 93

Actual plugging report: 8 5/8" set @ 250' w/175 sx. cwc. 5 1/2" set @
3578' w/200 sx. Top stage w/320 sx. to 500 P.S.I. Perf. 3084' - 3396'.
P.B.T.D 3558'. Squeezed bottom to 3396' w/75 sx. cement blend through
fiberglass. Loaded 5 1/2" from 1900' to surface with cement blend and
squeezed total system with total of 275 sxs. cement blend to Max. P.S.I.
400#. Close in P.S.I. 200#. Plug complete. Annulus of cement at
surface.

RECEIVED
STATE CORPORATION COMMISSION

Remarks:
Condition of casing(in hole): GOOD BAD Anhy.plug: YES NO
Bottom plug(in place): YES , CALC , NO Dakota plug: YES , NO
Plugged through TUBING , CASING . Elevation: GL

I did X / did not observe the plugging. Carl Goodrow

DH (agent)

DATE 7-21-93
WV. NO. 38181
6-10