

10-23 4-070074

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Number: 15-051-01,078-0001

NW NW SW /4 SEC. 18, 11 S, 18 W  
2350 feet from S section line  
4860 feet from E section line

Operator license# 31925

Lease: Jones "OWWO" Well # 1

Operator: Quality Well Service

County: Ellis 114.82

Address: 249 E. Beth  
Sterling, Kansas 67579

Well total depth 3533 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 1270 feet  
W/700 sxs.

ABAND. oil well X, Gas well, Input well, SWD, D&A

Plugging contractor: Quality Well Service License# 31925

Address: 249 E. Beth - Sterling, Kansas 67579

Company to plug at: Hour: 8:30 A.M. Day: 23 Month: October Year: 1997

Plugging proposal received from: Robert R. Price

Company: J.R.J. Resources Phone: 918-492-1694

Were: Pull casing and plug according to KCC District #4 regulations.  
8 5/8" 1270' w/700 sxs. 5 1/2" at 3480 w/250 sxs.  
J.R.J. Resources was operator but does not have current license.  
Plugged under Quality Well Service.

10-29-97

Plugging Proposal Received by: Herb Deines  
Plugging operations attended by agent? All [ X ], Part [ ], None [ ]

Completed: Hour: 2:00 P.M., Day: 23, Month: October, Year: 1997

Actual plugging report: Allied pumped 2 sxs Calicum Chloride with 100 sxs 60/40 pozmix - 10% gel with 200# hulls. Displaced to 2400'. Shot casing off at 2240' - pulled to 1500' - pumped 105 sxs 60/40 pozmix - 10% gel with 200# hulls. Pulled to 1000' - pumped 40 sxs with 200# hulls. Pulled to 500' - pumped 40 sxs - circulated cement PCOH. Topped off with 5 sxs.

Remarks:  
Condition of casing(in hole): GOOD X BAD  
Bottom plug(in place): YES X, CALC, NO  
Plugged through TUBING, CASING X.  
Anhy.plug: YES X NO  
Dakota plug: YES X, NO  
Elevation: 1912 GL

I did [ X ] / did not [ ] observe the plugging.

Richard Williams  
(agent)

Form CP-2/3

INVOICED

DATE OCT 30 1997

INV. NO. 49404