

6-16-87

To: 6 061266  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 13-051-06012-0000  
SW \_\_\_\_\_, SEC. 32, T 11 S, R18 (W/EX)

TECHNICIAN'S PLUGGING REPORT

Operator License # 5050

990 feet from S section line  
4950 feet from E section line

Operator: Hummon Corporation  
Name & Address: 400 One Main Place  
Wichita, Kansas 67202

Lease Name Johnson Z Well # 2  
County Ellis 117.16

Well Total Depth 3650 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 360'

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling Inc. License Number 6050

Address Box 347 Chase, Kansas 67524

Company to plug at: Hour: 10:00 AM Day: 16 Month: June Year: 19 87

Plugging proposal received from Ron Haver

(company name) Kelso Casing Pulling (phone) \_\_\_\_\_

were: Order 150 sks 65/35 Pozmix 10% Gel 2% Econolite, 5 sks. Hulls.

Plugging Proposal Received by Gilbert G. Scheck  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 11:30 AM Day: 16 Month: June Year: 19 87

ACTUAL PLUGGING REPORT 8 5/8" set at 360' w/200 sks. 5 1/2" set at 3649' w/150 sks.

Top perf. at 3278'. Plugged bottom w sand and 5 sks. cement to 3225'.

Shot pipe 6 times and recovered 0. Pumped in 5 1/2". 5 sks Hulls, 100 sks cement

w/100 Psi. Pumped in 8 5/8" - 25 sks cement w/300 Psi. Shots hole in casing  
from 2800' to 700'.

JUN 23 1987

Remarks: By Allied. (if additional description is necessary, use BACK of this form.)

STATE CORPORATION COMMISSION  
Wichita, Kansas

~~INVOICED~~

observe this plugging.

Signed Gilbert G. Scheck

DATE 6-24-87

INV. NO. 17326