

8-15 4-070115

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-109-20,672.0000

N2 SE SW /4 SEC. 13, 11 S, 34 W
1000 feet from S section line
3340 feet from E section line

Operator license# 4058

Lease: WasseMiller Well # 5

Operator: American Warrior

County: Logan 153.96

Address: P.O. Box 399
Garden City, Kansas 67846

Well total depth 4737 feet
Conductor Pipe: 0 inch @ 0 sxs.
Surface pipe 8 5/8 Inch @ 220 feet

ABAND. oil well, Gas well, Input well, SWD, D&A X

Plugging contractor: Discovery Drilling, Inc. License# 31548

Address: Hays, Kansas 67601

Company to plug at: Hour: A.M. Day: 15 Month: August Year: 1998

Plugging proposal received from: Tom Alm

Company: Discovery Drilling, Inc. Phone: 785-623-2920

Were: No ar buckle cut.
Ordered 200 sxs 60/40 pozmix - 6% gel - 1/4# floseal per sack - one 8 5/8" W.P.
Spot plug through drill pipe with heavy drilling mud between all plugs.

Plugging Proposal Received by: Rich Williams

Plugging operations attended by agent? All [], Part [], None [X]

Completed: Hour: 1:30 P.M. Day: 15, Month: August, Year: 1998

Actual plugging report: No ar buckle cut.

1st Plug at 2643' w/25 sxs. - Anhydrite 2628' - 2657'.

2nd Plug at 1557' w/100 sxs. - Dakota 1257'.

3rd Plug at 269' w/40 sxs.

4th Plug at 40 w/10 sxs. 8 5/8" W.P.

Rathole with 15 sxs.

Mousehole with 10 sxs.

Remarks:

Condition of casing(in hole): GOOD BAD Anhy. plug: YES X NO

Bottom plug(in place): YES, CALC, NO Dakota plug: YES X, NO

Plugged through TUBING, CASING. Elevation: 3157 GL

I did [] / did not [X] observe the plugging.

Richard Williams
(agent)

Form CP-2/3

INVOICED

10

DATE SEP 01 1998

WV. NO. 51233

8-15

JAN 29 1999

RECEIVED
KANSAS CORPORATION COMMISSION

AUG 31 1998

CONSERVATION DIVISION
WICHITA, KS