

10-31 4-032014

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

20491.0000
API number: 15-109-20,530

NW NW SE /4 SEC. 29, 11 S, 33 W
2310 feet from S section line
2310 feet from E section line

Operator license# 5393 Lease D & L Hubert Ent. well # 1

Operator: A.L. Abercrombie, Inc. County Logan

Address: R.R. 1 - Box 56 Well total depth 4665 feet ^{151.61}
Great Bend, Kansas 67530 Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 277 feet

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Allied Cement Company License#

Address: Oakley, Kansas

Company to plug at: Hour: A.M. Day: 31 Month: October Year: 94

Plugging proposal received from: Bill Sowels

Company: A.L. Abercrombie, Inc. Phone:

Were: Order 215 sxs. 60/40 pozmix - 10% gel - 500# hulls.
Allied Cement Company.

RECEIVED
KANSAS CORPORATION COMMISSION

NOV 10 1994

CONSERVATION DIVISION
WICHITA, KS

Plugging Proposal Received by: Carl Goodrow
Plugging operations attended by agent? All[], Part[X], None[]

Completed: Hour: 10:15A.M., Day: 31, Month: October, Year: 94

Actual plugging report: 8 5/8" set @ 277' w/200 sxs. cwc. 4 1/2" set @
4415' w/150 sxs. PBD 4385'. Perf. @ 1630' - 1631' cwc. w/250 sxs.
Prod. perf. 4241' - 4244'. Squeezed 4 1/2" w/200 sxs. cement blend
w/250# hulls mixed in to Max. P.S.I. 1000#. Close in P.S.I. 1000#.
Tested 8 5/8" w/10 sxs. to Max. 500#. Close in 500#.

Remarks:
Condition of casing(in hole): GOOD X BAD Anhy.plug: YES X NO
Bottom plug(in place): YES , CALC X, NO Dakota plug: YES X, NO
Plugged through TUBING , CASING X. Elevation: GL

I ~~did~~ ^{did not} observe the plugging. Carl Goodrow

DATE 11-18-94
WELL NO. 41715

(agent)
Form CP-2/3