

6 031341

2-8

109-20,482-0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-

E/2 SE, SEC. 14, T 11 S, R 33 W/4E

1320 feet from S section line

660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8541

Lease Name Ahrens Well # Z-1

Operator: Petex Inc.

County Logan 152.58

Name & Address 1111 S. Glenstone #1-104

Well Total Depth 4695 feet

Springfield Missouri 65804

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 265

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Blue Goose Drilling License Number 5104

Address

Company to plug at: Hour: PM Day: 8 Month: Feb Year: 19 90

Plugging proposal received from Martin Miller

(company name) Blue Goose (phone)

were: 8 5/8" set at 265' w/180 sks. Circ hole w/no less than 36 vis mud

w/no loss or gain of fluid in hole. Keep hole full and balance plugs w/mud.

Order 180 sks 60/40 poz 6% gel 3% cc. 8 5/8" wiper plug. B. J. Titan Cement Co.

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 1:00PM Day: 8 Month: Feb Year: 19 90

ACTUAL PLUGGING REPORT Spot plugs w/d.p. at 2625' w/25 sks.

1800' w/100 sks and hulls.

310' w/40 sks

40' w/10 sks and wiper plug

Circ. 15 sks in rathole w/joint of pipe.

MAR 15 1990

Remarks: Elev. 3119' Anhy 2610' - 38'

(If additional description is necessary, use BACK of this form.)

INVOICED

(XXXXXX did not) observe this plugging.

DATE 3-16-90

Signed Carl Goodrow (TECHNICIAN) Carl Goodrow

INV. NO. 27697