

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-109-20683-00-00  
Spot: NENENE Sec/Twnshp/Rge: 29-11S-33W  
4950 feet from S Section Line, 330 feet from E Section Line  
Lease/Unit Name: LOFTUS Well Number: 1  
County: LOGAN Total Vertical Depth: 4750 feet

Operator License No.: 30407  
Operator Name: BLACK PETROLEUM COMPANY  
Address: PO BOX 12922  
WICHITA, KS 67277 11/3

Conductor Pipe: Size feet:  
Surface Casing: Size 8.625 feet: 274 235 SXS CMT.  
Production: Size feet:  
Liner: Size feet: 154.38

Well Type: DH UIC Docket No: Date/Time to Plug: 11/03/2000 2:15 PM  
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.  
Proposal Revd. from: BILL WYNN Company: MURFIN DRILLING CO., INC. Phone: (316) 267-3241

Proposed Plugging Method: Ordered 200 sxs 60/40 pozmix - 6% gel.  
Plug according to KCC Rules and Regulations.

Plugging Proposal Received By: ROGER MOSES Witness Type: Plugging Operations Were Not Witnessed  
Date/Time Plugging Completed: 11/03/2000 5:30 PM KCC Agent: ROGER MOSES

Actual Plugging Report:

Set 8 5/8" S.P. at 274' w/235 sxs cement.  
1st. Plug at 2615' w/25 sxs cement. - Anhydrite 2600' - 2630'.  
2nd. Plug at 1630' w/100 sxs cement. - Dakota 1330' - 1630'.  
3rd. Plug at 325' w/40 sxs cement. Surface pipe at 274'.  
4th. Plug at 40' w/10 sxs cement. 8 5/8" Wiper plug.  
15 sxs in rathole.  
10 sxs in mousehole.  
Total of 200 sxs 60/40 pozmix - 10% gel and 1/4# flocele per sack.

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 4 2000  
CONSERVATION DIVISION  
Wichita, Kansas

Remarks: ALLIED CEMENTING COMPANY

Plugged through: DP

District: 04

Signed Roger L. Moses  
(TECHNICIAN)

110

INVOICED

DATE: 12/5/00

WELL NO: 2001061062

NOV 30 2000