

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
MAY 14 1970
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Three G Oil, Inc.
 Complete Address 700 Brown Bldg., Wichita, Kansas 67202
 Lease Name Armbrister Well No. 1
 Location W/2 W/2 SE Sec. 6 Twp. 11 Rge. (E) (W) 19
 County Ellis Total Depth 3740'
 Abandoned Oil Well XX Gas Well Input Well SWD Well D & A
 Other well as hereafter indicated
 Plugging Contractor Sun Oil Well Cementing
 Address Hays, Kansas License No.
 Operation Completed: Hour 3:30P Day 12 Month 5 Year 1970

The above well was plugged as follows:

RTD 3740' 8 5/8 csg set at 206' cwc 150 sk.

5 1/2 csg set at 3570' cw 100 sk cmt.

5 1/2 csg perf. (3450-3452) & (3495-3497)

5 1/2 csg DV tool set at 1524 and cemented with 500 sk cmt.

No pipe recovered.

Pumped thru 5 1/2 plug container with 30 sk poz 6% gel, 30 sk gel W/5 sk hulls, plug
and 60 sk poz 6% gel. Max. pres. 2500 lbs.

Checked amulus (8 5/8- 5 1/2) .

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Geo F. Massey
Well Plugging Supervisor

DATE

5/14/70

INV. NO.

1888-W