

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

OCT - 6 1967

Operator's Full Name Three G Oil, Inc.

Complete Address: 1101 Wichita Plaza Wichita, Kansas

Lease Name Armbrister Well No. 2

Location SE SW SE Sec. 6 Twp. 11 Rge. 19 (E) (W) X

County Ellis Total Depth 3724

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: H-30 Drlg. Inc.

Address: Wichita, Kansas License No. _____

Operation Completed: Hour 8:30P Day 26 Month 9 Year 1967

The Above well was plugged as follows:

RTD 3724' 10 3/4 csg set at 206' cwc.

Gunned pits, circulated heavy mud, set cementing plug at 800' and displaced 100 sc cem. thru drill pipe. Heavy mud to 210' set cementing plug and displaced 25 sc cement thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and 10 sc cement to base of cellar. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 10-2-67
INV. NO. 6440-W

Signed: Ray F. Murray
Well Plugging Supervisor