

KANSAS

14

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

RECEIVED  
MAY 27 1967  
STATE CORPORATION COMMISSION

Operator's Full Name Rains & Williamson Oil Company

Complete Address: 1425 Wichita Plaza Wichita, Kansas

Lease Name Vine "A" Well No. 3

Location SW SE NE Sec. 35 Twp. 11 Rge. 19 (E) (W) X

County Ellis Total Depth 3655

Abandoned Oil Well X Gas Well        Input Well        SWD Well        D & A       

Other well as hereafter indicated:       

Plugging Contractor: Knight Casing Pulling

Address: Box 504 Chase, Kansas License No. 436

Operation Completed: Hour 11 A Day 9 Month 5 Year 1967

The Above well was plugged as follows:

Total Depth 3655' 8 5/8 csg set at 174' cwc.

5 1/2 csg set at 3640' cw 100 sc cement.

Dakato squeezed with 200 sc cement.

Sand back to 3600' and dumped 5 sc cement with dump bailer.

Recov. 627' of 5 1/2 csg.

Mud to 255'. Set plug and 10' rock bridge.

Filled to surface with 3 yds reagymix cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED  
DATE 5/11/67  
INV. NO. 5204-W

Signed: [Signature]  
Well Plugging Supervisor